

# QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	TRAINING	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							104				104		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
							3800				3800		EACH	LINE STRIPING TARGETS	646.76	32			
							5620				5620		SY	GEOTEXTILE UNDER STONE FILL	649.31	57			
							1600				1600		SY	GEOTEXTILE FOR SILT FENCE	649.51	26			
							435				435		LB	SEED	651.15	2.4			
							3625				3625		LB	FERTILIZER	651.18	EST.			
							15				15		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
							15				15		TON	HAY MULCH	651.25	EST.			
							230				230		CY	TOPSOIL	651.35	EST.			
							540				540		SY	GRUBBING MATERIAL	651.40	10			
							17550				17550		SY	TEMPORARY EROSION MATTING	653.20	193			
							1900				1900		LF	EROSION LOG	653.60	85			
							1020				1020		SF	TRAFFIC SIGNS, TYPE A	675.20	8.28			
							650				650		LB	TUBULAR STEEL SIGN POST	675.33	7.8			
							3040				3040		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	37			
							8				8		EACH	FOUNDATION FOR TUBULAR STEEL POST	675.43	-			
							166				166		EACH	REMOVING SIGNS	675.50	-			
							60				60		EACH	DELINEATOR WITH STEEL POST	676.10	3			
							60				60		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-			
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
							116200				116200		SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	1109			
							2770				2770		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	31			
							116200				116200		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	1109			
							34700				34700		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680				
							2080				2080		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	20			
							195				195		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	2			
							435				435		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	3			
							1470				1470		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	18			

PROJECT NAME: VERSHIRE-THETFORD  
 PROJECT NUMBER: STP 2911(I)  
 FILE NAME: pl0c224.dgn PLOT DATE: 1/29/2013  
 PROJECT LEADER: PTS DRAWN BY: SNG  
 DESIGNED BY: NULL CHECKED BY: PTS  
 IPARM FILE NAME: IOC224\_I2 SHEET 12 OF 232