

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES					TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
	ROADWAY	ROADWAY (NO FEDERAL/ STATE)	BRIDGE	FULL C. E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS
							BEGIN OPTION EE					
	45				45	EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-	688	SY	DITCH CLEANING
	45				45	EACH	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493	-	7290	SY	SLOPE EROSION PREVENTION
	45				45	EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-	122	SY	ROUNDING
							END OPTION EE			8100	SY	TOTAL
							BEGIN OPTION FF					TEMPORARY EROSION MATTING
	130				130	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	2	5333	SY	DITCH CLEANING
	130				130	LF	DURABLE CROSSWALK MARKING, EPOXY PAINT	646.503	2	400	SY	GUARDRAIL END SECTIONS
	130				130	LF	DURABLE CROSSWALK MARKING, POLYUREA	646.504	2	67	SY	ROUNDING
							END OPTION FF			5800	SY	TOTAL
	243900				243900	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	2352			
	209800				209800	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	2028			
	250				250	LF	TEMPORARY 8 INCH WHITE LINE, PAINT	646.642	10			
	740				740	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	12			
	180				180	EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
	520				520	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	8			
	3450				3450	EACH	LINE STRIPING TARGETS	646.76	40			
	8100				8100	SY	GEOTEXTILE UNDER STONE FILL	649.31	122			
	4650				4650	SY	GEOTEXTILE FOR SILT FENCE	649.51	83			
	1150				1150	LB	SEED	651.15	EST.			
	7000				7000	LB	FERTILIZER	651.18	EST.			
	30				30	TON	AGRICULTURAL LIMESTONE	651.20	EST.			
	30				30	TON	HAY MULCH	651.25	EST.			
	5600				5600	CY	TOPSOIL	651.35	EST.			
	5250				5250	SY	GRUBBING MATERIAL	651.40	52			
	5800				5800	SY	TEMPORARY EROSION MATTING	653.20	67			
	13300				13300	LF	BARRIER FENCE	653.50	106			
	13300				13300	LF	PROJECT DEMARCATION FENCE	653.55	106			
	10400				10400	LF	EROSION LOG	653.60	125			
	770				770	SF	TRAFFIC SIGNS, TYPE A	675.20	5.4			
	200				200	LB	TUBULAR STEEL SIGN POST	675.33	10			
	2365				2365	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	25			
	2				2	EACH	FOUNDATION FOR TUBULAR STEEL POST	675.43	-			
	182				182	EACH	REMOVING SIGNS	675.50	-			
	1				1	EACH	ERECTING SALVAGED SIGNS	675.60	-			
	23				23	EACH	DELINEATOR WITH STEEL POST	676.10	-			
	15				15	EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-			
	1				1	EACH	TRAFFIC CONTROL SIGNAL SYSTEM, INTERSECTION	678.15	-			

PROJECT NAME: ESSEX-WESTFORD
PROJECT NUMBER: STP 2912(1)

FILE NAME: p10c226.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p10c226qs03.i

PLOT DATE: 2/20/2013
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 9 OF 239