STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 01

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	1.3	1.7	1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0	3.5	4.0	5.0	7.6	9.0	10.8	14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
ESSEX																																											
0+91, RT	WEST VERMONT 15 / NORTH VERMONT 128	1	24	12	2.00						2						X	X																					*2	M3-4 GREEN ON WHITE			E-136B
		1	24	12	2.00																																		M3-1 GREEN ON WHITE			E-136B
		1	24	24	4.00																																		MI-5			E-136B
		1	30	24	5.00																																		MI-5			E-136B
		1	21	15	2.19																																		M6-1 GREEN ON WHITE			E-136B
		1	21	15	2.19																																		M6-1 GREEN ON WHITE			E-136B
0+91, LT		1	9	15	0.94																																		R10-3e MOUNT ON PEDESTRIAN SIGNAL POLE	X		
0+94, LT	EAST VERMONT 15 / WEST VERMONT 15	1	24	12	2.00						2					X		X																					*2	M3-2 GREEN ON WHITE			E-136B
		1	24	12	2.00																																		M3-4 GREEN ON WHITE			E-136B
		1	24	24	4.00																																		MI-5			E-136B
		1	24	24	4.00																																		MI-5			E-136B
		1	21	15	2.19																																		M6-1 GREEN ON WHITE			E-136B
		1	21	15	2.19																																		M6-3 GREEN ON WHITE			E-136B
0+96, RT		1	9	15	0.94																																		R10-3e MOUNT ON PEDESTRIAN SIGNAL POLE	X		
I+00, RT	Westford 8 / Fairfax 12 / Jericho 3 / NORTH VERMONT 128 / EAST VERMONT 15	1	72	12	6.00																																		VDI-1a		66	
		1	72	12	6.00																																		VDI-1a		66	
		1	72	12	6.00																																		VDI-1a		66	
		1	24	12	2.00						2															2	190												M3-1 GREEN ON WHITE			E-136B
		1	24	12	2.00																																		M3-2 GREEN ON WHITE			E-136B
		1	24	24	4.00																																		MI-5			E-136B
		1	30	24	5.00																																		MI-5			E-136B
		1	21	15	2.19																																		M6-3 GREEN ON WHITE			E-136B
		1	21	15	2.19																																		M6-1 GREEN ON WHITE			E-136B
I+20, RT	NORTH VERMONT 128	1	24	12	2.00						1					X		X																						M3-1 GREEN ON WHITE			E-136B
		1	30	24	5.00																																		MI-5			E-136B
2+60, RT	SPEED LIMIT 30	1	24	30	5.00						1					X		X																						R2-1	X		
3+00, LT	Essex Jct 3 / Burlington 10 / Jericho 3	1	72	12	6.00																																		VDI-1a USE SOIL BEARING SLIP BASES. PAID AS ITEM 900.620 SPECIAL		66	
		1	72	12	6.00						2						X	X																					VDI-1a PROVISION (SOIL BEARING SLIP BASE) (2 1/2").		66	
		1	72	12	6.00																																		VDI-1a		66	
											FT	FT	FT		FT	FT	FT		EA	LB	LB	LB			LB	LB	LB	LB														
																61	64									190																	
TOTALS			SF	SF	EA.	SF			FT		FT									LB			EA.		LB				EA.	EA.	LB									
			101.02								125												2		190																	

"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #1

PROJECT NAME: ESSEX-WESTFORD
PROJECT NUMBER: STP 2912(I)

FILE NAME: p10c226.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p10c226tss01.i

PLOT DATE: 2/20/2013
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 51 OF 239