STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 08

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 (1.88)	SQUARE STEEL (in) lb/ft 2.0 (2.42)	SQUARE STEEL (in) lb/ft 2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 (1.3)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 (1.7)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD (1.7)	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 (7.6)	TUBULAR STEEL Ø (in) lb/ft 3.5 (9.0)	TUBULAR STEEL Ø (in) lb/ft 4.0 (10.8)	TUBULAR STEEL Ø (in) lb/ft 5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM BOOK	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
ESSEX (CONT.)																																					
60+10, LT		1	36	36	9.00						2					X		X															WI-IL		67	
	25 M.P.H.	1	18	18	2.25																												WI3-IP	X		
60+10, RT		1	36	36	9.00						2					X		X															WI-IL		67	
	25 M.P.H.	1	18	18	2.25																												WI3-IP	X		
63+00, LT	SPEED LIMIT 50	1	24	30	5.00						1					X		X															R2-1	X		
63+50, RT	Westford 7	1	72	12	6.00						2					X		X															VD1-1a		66	
	Jericho 2	1	72	12	6.00																												VD1-1a		66	
	1280 0406 0120	1	6	10	0.42																												VD-700			E-138
65+00, LT	SOUTH VERMONT 128	1	24	12	2.00						1					X		X															M3-3 GREEN ON WHITE			E-136B
		1	30	24	5.00																												M1-5			E-136B
65+03, RT		1	48	24	8.00						2					X		X															W1-6L	X		
65+19, RT		1	48	24	8.00						2					X		X															W1-6R	X		
65+53, RT		1	48	24	8.00						2					X		X															W1-6R	X		
65+68, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															VR-017			E-141
66+23, RT		1	48	24	8.00						2					X		X															W1-6L	X		
TOTALS					SF 83.92	SF	EA.	SF				FT	FT	FT	FT	FT 256	FT		EA	LB	LB	LB		LB	LB	LB	LB									
												FT			FT 256					LB			EA.	LB				EA.	EA.	LB						

"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #8

PROJECT NAME: ESSEX-WESTFORD
PROJECT NUMBER: STP 2912(1)

FILE NAME: p10c226.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p10c226tss08.i

PLOT DATE: 2/20/2013
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 58 OF 239