


VIP Camera Interface Panel



For 1 to 6 cameras

The Traficon Camera Interface Panel (CIP) provides power and transient voltage suppression for the video detection system.



Pictured: 2285-121



- **DIMENSIONS:** 170 CIP: 19" X 4" NEMA CIP: 14" X 6"
- **CONSTRUCTION:** 5052 Aluminum
- **POWER:** Multi 9 System (C60), Mini Circuit Breakers, 120 VAC, 3 amp/camera
- **VIDEO:** Edco CX06-M "Mini" Suppressor

Model	Description	Model	Description
2285-121	170 CIP for 1 Camera	2285-101	NEMA CIP for 1 Camera
2285-122	170 CIP for 2 Cameras	2285-102	NEMA CIP for 2 Cameras
2285-123	170 CIP for 3 Cameras	2285-103	NEMA CIP for 3 Cameras
2285-124	170 CIP for 4 Cameras	2285-104	NEMA CIP for 4 Cameras
2285-125	170 CIP for 5 Cameras	2285-105	NEMA CIP for 5 Cameras
2285-126	170 CIP for 6 Cameras	2285-106	NEMA CIP for 6 Cameras