




Black Finish with 9" x 15" Sign




**Technical Specification**

BS Size	5 x 12 x 1 3/4"
BS Weight	7.0 lbs
Power (rest)	0.18W @ 120 VAC
Current (rest)	4 mA @ 120 VAC
Max Power	1.68 W
Switch life	100 x 10 <sup>6</sup>
Operational force	< 3lbf
Operating Temp Range	-40C to +85C
Max Volume	100dB @ 1m
AGC Range	Adjustable 0 - 5dB over ambient
Audio Output Options	Default plus 4 options
LED	3000 mcd, 160 degree viewing angle
Volume control	Fully adjustable, independent channels
Reporting	Pedestrian Usage, Event Logging, System Evaluation
Synchronicity	Beaconing, Group Walk
Night Mode	Volume, Recall
Selectable Options (options selected via top USB connection via a menu drive utility)	EP AFS, Vib Pulse Call, Recall, Beaconing, Group Walk, Walk time out, Locator Temp, EP Time, Vib Intensity
Size	5 X 7", 5 X 9", 9 X 12", 9 X 15"
Warranty	3 year
Functionality	MUTCD 2003 4E, TAC
Transient Voltage Protection	NEMA TS2
Mechanical Shock and Vibration	NEMA TS2

Interface	Windows Utility
Audio File Update	USB
Data Format	CSV
Firmware Upgrade	USB

Input voltage	85 - 135 VAC
Output voltage	12V DC
Connection	4 wire
Dimension	2 3/4 x 3 1/2 x 1 7/8"



Additional information can be found at: [www.pedsafety.com](http://www.pedsafety.com)

This document is copyright © May 7, 2012 Campbell Company. All rights reserved. This document is provided for information purposes only; contents are subject to change without notice.