

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	BRIDGE	FULL C.E. ITEMS	GOV'T NON PARTIC.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1550					1550		LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652	59			TOPSOIL
						1250					1250		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	11	110	SY	ITEM DETAIL SHEET 4
						210					210		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	9	350	SY	GUARDRAIL DETAIL SHEET 2
						12500					12500		EACH	LINE STRIPING TARGETS	646.76	62	10	SY	ROUNDING
						14500					14500		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	EST.	470	SY	TOTAL
						2025					2025		SY	GEOTEXTILE FOR SILT FENCE	649.51	49			TEMPORARY EROSION MATTING
						1540					1540		LB	SEED	651.15	EST.	2622	SY	ITEM DETAIL SHEET 4
						3100					3100		LB	FERTILIZER	651.18	EST.	2124	SY	DITCH CLEANING DETAIL SHEET
						13					13		TON	AGRICULTURAL LIMESTONE	651.20	EST.	1750	SY	GUARDRAIL DETAIL SHEET 2
						13					13		TON	HAY MULCH	651.25	EST.	154	SY	ROUNDING
						470					470		CY	TOPSOIL	651.35	EST.	6650	SY	TOTAL
						36500					36500		SY	GRUBBING MATERIAL (2")	651.40	259			SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)
						2700					2700		SY	GRUBBING MATERIAL (6")	651.40	78	9661	TON	MAINLINE
						6650					6650		SY	TEMPORARY EROSION MATTING	653.20	154	3335	TON	LEVELING
						4500					4500		LF	BARRIER FENCE	653.50	92	208	TON	SIDE ROADS
						4500					4500		LF	EROSION LOG	653.60	92	157	TON	PULL OFFS
						330					330		SF	TRAFFIC SIGNS, TYPE A	675.20	12.89	139	TON	ROUNDING
						2669					2669		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	EST.	13500	TON	TOTAL
						183					183		EACH	REMOVING SIGNS	675.50	-			
						92					92		EACH	ERECTING SALVAGED SIGNS	675.60	-			
						70					70		EACH	DELINEATOR WITH STEEL POST	676.10	-			
						68					68		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-			
						1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
						3					3		EACH	SPECIAL PROVISION (CORING CONCRETE)	900.620	-			
						5					5		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-			
						1					1		EACH	SPECIAL PROVISION (GNSS CONSTRUCTION INSPECTION EQUIPMENT)	900.620	-			
						5225					5225		LF	SPECIAL PROVISION (BARRIER FOR TEMPORARY BARRIER PROTECTION)	900.640	-			
						12540					12540		LF	SPECIAL PROVISION (BOX BEAM GUARDRAIL W/7 FEET POSTS)	900.640	-			
						1					1		LS	SPECIAL PROVISION (GPS MACHINE CONTROL GRADING)	900.645	-			
						1					1		LS	SPECIAL PROVISION (INTELLIGENT COMPACTION FOR BITUMINOUS CONCRETE)	900.645	-			
						1					1		LS	SPECIAL PROVISION (INTELLIGENT COMPACTION FOR SUBBASE/RSB)	900.645	-			
						118000					118000		SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	527			
						3550					3550		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	40.5			
						102000					102000		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE)	900.675	1380			
						118000					118000		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	527			
						4200					4200		TON	SPECIAL PROVISION (AGGREGATE TO MEET COLD MIXED GRADATION)	900.680	94			
						13500					13500		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	139			
						28000					28000		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)	900.680	627			
						2725					2725		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	29			
						270					270		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	6			

PROJECT NAME: BETHEL -RANDOLPH
 PROJECT NUMBER: STP 2921(I)
 FILE NAME: z10c244quant.dgn PLOT DATE: 4/23/2015
 PROJECT LEADER: C. LATHROP DRAWN BY: S. LAMPHERE
 DESIGNED BY: S. LAMPHERE CHECKED BY: C. LATHROP
 QUANTITY SHEET 3 SHEET 15A OF 211