STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. 277+50 RT BETHEL	BRIDGE ICES BEFORE ROAD	1	30	30			1				1					X		X																W8-13		
STA. 281+33 LT BETHEL	EMERGENCY VEHICLES ENTERING	1	36	36			1				2					X		X															VW-544M		E-154
STA. 282+26 RT BETHEL	Spring Hollow Rd	1	66	12			1				2					X		X															D3-1		
STA. 284+02 LT BETHEL		1	12	36			1				1					X		X																OM3-L		
STA. 284+04 RT BETHEL	BRIDGE 38 VT 12	1	6	10	0.42						1				X			X															VD-701		T-42
STA. 284+06 RT BETHEL		1	12	36	3.00						1					X		X																OM3-R		
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF 8	LF 105	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 3.42	SF	EA. 4	SF				LF			LF 113					LB			EA. -	LB				EA.	EA.	LB					

PROJECT NAME: BETHEL-RANDOLPH
PROJECT NUMBER: STP 2921(1)

FILE NAME: z10c244tsss.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: S. LAMPHERE
TRAFFIC SIGN SUMMARY SHEET 15

PLOT DATE: 4/23/2015
DRAWN BY: S. LAMPHERE
CHECKED BY: C. LATHROP
SHEET 100 OF 211