

| Element | Point Type | Station | Northing | Easting | Radius | Length | Delta / Theta | Rotation Direction | Maximum Banking | Design Speed |
|-----------------|------------|-----------|-------------|-------------|--------|--------|---------------|--------------------|-----------------|--------------|
| Tangent | POB | 124+00.00 | 486120.7514 | 1602818.086 | | | | | | |
| | PC | 126+73.12 | 486321.2912 | 1602632.673 | | | | | | |
| Bethel Curve #1 | PC | 126+73.12 | 486321.2912 | 1602632.673 | 10000 | 77.46 | 0°26'37.76" | Right | NC | 35 |
| | PI | 127+11.85 | 486349.7297 | 1602606.38 | | | | | | |
| | CC | | 493110.0044 | 1609975.246 | | | | | | |
| | PT | 127+50.58 | 486378.371 | 1602580.308 | | | | | | |
| Tangent | PT | 127+50.58 | 486378.371 | 1602580.308 | | | | | | |
| | PC | 136+31.98 | 487030.1598 | 1601986.983 | | | | | | |
| Bethel Curve #2 | PC | 136+31.98 | 487030.1598 | 1601986.983 | 5500 | 442.34 | 4°36'28.76" | Right | 0.022 | 50 |
| | PI | 138+53.27 | 487193.8 | 1601838.02 | | | | | | |
| | CC | | 490732.5582 | 1606054.199 | | | | | | |
| | PT | 140+74.31 | 487368.8787 | 1601702.686 | | | | | | |
| Tangent | PT | 140+74.31 | 487368.8787 | 1601702.686 | | | | | | |
| | PC | 147+92.00 | 487936.6969 | 1601263.768 | | | | | | |
| Bethel Curve #3 | PC | 147+92.00 | 487936.6969 | 1601263.768 | 10000 | 53.06 | 0°18'14.52" | Right | NC | 50/45 |
| | PI | 148+18.53 | 487957.6886 | 1601247.542 | | | | | | |
| | CC | | 494052.4777 | 1609175.609 | | | | | | |
| | PT | 148+45.06 | 487978.7661 | 1601231.427 | | | | | | |
| Tangent | PT | 148+45.06 | 487978.7661 | 1601231.427 | | | | | | |
| | PC | 149+68.44 | 488076.7836 | 1601156.488 | | | | | | |
| Bethel Curve #4 | PC | 149+68.44 | 488076.7836 | 1601156.488 | 1515 | 109.79 | 4°09'08.25" | Right | 0.061 | 50 |
| | PI | 150+23.36 | 488120.4138 | 1601123.13 | | | | | | |
| | CC | | 488996.9509 | 1602360.031 | | | | | | |
| | PCC | 150+78.24 | 488166.3448 | 1601093.02 | | | | | | |
| Bethel Curve #4 | PCC | 150+78.24 | 488166.3448 | 1601093.02 | 600 | 254.05 | 24°15'39.80" | Right | 0.08 | 45 |
| | PI | 152+07.20 | 488274.1983 | 1601022.315 | | | | | | |
| | CC | | 488495.2978 | 1601594.806 | | | | | | |
| | PT | 153+32.30 | 488401.5786 | 1601002.171 | | | | | | |
| Tangent | PT | 153+32.30 | 488401.5786 | 1601002.171 | | | | | | |
| | PC | 154+65.90 | 488533.5417 | 1600981.302 | | | | | | |
| Bethel Curve #5 | PC | 154+65.90 | 488533.5417 | 1600981.302 | 10000 | 85.59 | 0°29'25.41" | Right | NC | 50 |
| | PI | 155+08.70 | 488575.8114 | 1600974.618 | | | | | | |
| | CC | | 490095.5274 | 1610858.559 | | | | | | |
| | PT | 155+51.49 | 488618.1367 | 1600968.295 | | | | | | |
| Tangent | PT | 155+51.49 | 488618.1367 | 1600968.295 | | | | | | |
| | PC | 162+21.18 | 489280.4827 | 1600869.355 | | | | | | |
| Bethel Curve #6 | PC | 162+21.18 | 489280.4827 | 1600869.355 | 2673 | 156.62 | 3°21'25.36" | Right | 0.041 | 50/40 |
| | PI | 162+99.51 | 489357.9531 | 1600857.783 | | | | | | |
| | CC | | 489675.3892 | 1603513.023 | | | | | | |
| | PCC | 163+77.80 | 489435.9682 | 1600850.767 | | | | | | |
| Bethel Curve #6 | PCC | 163+77.80 | 489435.9682 | 1600850.767 | 450 | 272.58 | 34°42'20.07" | Right | 0.08 | 50/40 |
| | PI | 165+18.41 | 489576.0173 | 1600838.172 | | | | | | |
| | CC | | 489476.2748 | 1601298.958 | | | | | | |
| | PT | 166+50.38 | 489698.3211 | 1600907.556 | | | | | | |
| Tangent | PT | 166+50.38 | 489698.3211 | 1600907.556 | | | | | | |
| | PC | 168+97.80 | 489913.5224 | 1601029.642 | | | | | | |
| Bethel Curve #7 | PC | 168+97.80 | 489913.5224 | 1601029.642 | 550 | 369.71 | 38°30'50.24" | Left | 0.08 | 50/40 |
| | PI | 170+89.94 | 490080.6456 | 1601124.453 | | | | | | |
| | CC | | 490184.9124 | 1600551.262 | | | | | | |
| | PT | 172+67.50 | 490270.4513 | 1601094.57 | | | | | | |
| Tangent | PT | 172+67.50 | 490270.4513 | 1601094.57 | | | | | | |
| | PC | 174+09.64 | 490410.8607 | 1601072.463 | | | | | | |
| Bethel Curve #8 | PC | 174+09.64 | 490410.8607 | 1601072.463 | 553 | 269.01 | 27°52'20.03" | Right | 0.06 | 40/50 |
| | PI | 175+46.87 | 490546.4146 | 1601051.122 | | | | | | |
| | CC | | 490496.8661 | 1601618.734 | | | | | | |
| | PCC | 176+78.66 | 490676.2205 | 1601095.627 | | | | | | |
| Bethel Curve #8 | PCC | 176+78.66 | 490676.2205 | 1601095.627 | 1250 | 214.37 | 9°49'33.95" | Right | 0.055 | 40/50 |
| | PI | 177+86.11 | 490777.8617 | 1601130.476 | | | | | | |
| | CC | | 490270.8083 | 1602278.058 | | | | | | |
| | PT | 178+93.03 | 490872.0647 | 1601182.16 | | | | | | |

| Element | Point Type | Station | Northing | Easting | Radius | Length | Delta / Theta | Rotation Direction | Maximum Banking | Design Speed |
|------------------|------------|-----------|-------------|-------------|--------|--------|---------------|--------------------|-----------------|--------------|
| Tangent | PT | 178+93.03 | 490872.0647 | 1601182.16 | | | | | | |
| | PC | 184+76.60 | 491383.69 | 1601462.86 | | | | | | |
| Bethel Curve #9 | PC | 184+76.60 | 491383.69 | 1601462.86 | 1430 | 245.26 | 9°49'36.31" | Left | 0.063 | 50 |
| | PI | 185+99.53 | 491491.4654 | 1601521.99 | | | | | | |
| | CC | | 492071.5272 | 1600209.153 | | | | | | |
| | PCC | 187+21.86 | 491607.7513 | 1601561.859 | | | | | | |
| Bethel Curve #9 | PCC | 187+21.86 | 491607.7513 | 1601561.859 | 800 | 222.07 | 15°54'17.01" | Left | 0.08 | 50 |
| | PI | 188+33.61 | 491713.4651 | 1601598.103 | | | | | | |
| | CC | | 491867.2063 | 1600805.101 | | | | | | |
| | PCC | 189+43.93 | 491825.0644 | 1601603.99 | | | | | | |
| Bethel Curve #9 | PCC | 189+43.93 | 491825.0644 | 1601603.99 | 8400 | 215.55 | 1°28'12.86" | Left | NC | 50 |
| | PI | 190+51.71 | 491932.6949 | 1601609.667 | | | | | | |
| | CC | | 492267.5544 | 1593215.653 | | | | | | |
| | PT | 191+59.48 | 492040.4356 | 1601612.582 | | | | | | |
| Tangent | PT | 191+59.48 | 492040.4356 | 1601612.582 | | | | | | |
| | PC | 193+83.16 | 492264.037 | 1601618.629 | | | | | | |
| Bethel Curve #10 | PC | 193+83.16 | 492264.037 | 1601618.629 | 20000 | 43.63 | 0°07'30.00" | Left | NC | 50 |
| | PI | 194+04.98 | 492285.8455 | 1601619.219 | | | | | | |
| | CC | | 492804.7961 | 1581625.941 | | | | | | |
| | PT | 194+26.79 | 492307.6553 | 1601619.762 | | | | | | |
| Tangent | PT | 194+26.79 | 492307.6553 | 1601619.762 | | | | | | |
| | PC | 199+67.21 | 492847.9063 | 1601633.195 | | | | | | |
| Bethel Curve #11 | PC | 199+67.21 | 492847.9063 | 1601633.195 | 20000 | 64.69 | 0°11'07.13" | Right | NC | 50 |
| | PI | 199+99.55 | 492880.2398 | 1601633.999 | | | | | | |
| | CC | | 492350.7655 | 1621627.015 | | | | | | |
| | PT | 200+31.90 | 492912.5706 | 1601634.907 | | | | | | |
| Tangent | PT | 200+31.90 | 492912.5706 | 1601634.907 | | | | | | |
| | PC | 205+72.51 | 493452.9704 | 1601650.093 | | | | | | |
| Bethel Curve #12 | PC | 205+72.51 | 493452.9704 | 1601650.093 | 670 | 90.57 | 7°44'43.59" | Left | 0.06 | 45/35 |
| | PI | 206+17.87 | 493498.308 | 1601651.367 | | | | | | |
| | CC | | 493471.7908 | 1600980.358 | | | | | | |
| | PCC | 206+63.08 | 493543.4037 | 1601646.52 | | | | | | |
| Bethel Curve #12 | PCC | 206+63.08 | 493543.4037 | 1601646.52 | 445 | 376.57 | 48°29'04.74" | Left | 0.06 | 45/35 |
| | PI | 208+63.47 | 493742.642 | 1601625.101 | | | | | | |
| | CC | | 493495.84 | 1601204.069 | | | | | | |
| | PT | 210+39.65 | 493858.6637 | 1601461.72 | | | | | | |
| Tangent | PT | 210+39.65 | 493858.6637 | 1601461.72 | | | | | | |
| | PC | 212+22.49 | 493964.5266 | 1601312.643 | | | | | | |
| Bethel Curve #13 | PC | 212+22.49 | 493964.5266 | 1601312.643 | 785 | 951.88 | 69°28'32.74" | Right | 0.06 | 45 |
| | PI | 217+66.82 | 494279.6873 | 1600868.834 | | | | | | |
| | CC | | 494604.564 | 1601767.151 | | | | | | |
| | PCC | 221+74.37 | 494805.8218 | 1601008.389 | | | | | | |
| Bethel Curve #13 | PCC | 221+74.37 | 494805.8218 | 1601008.389 | 2520 | 259.64 | 5°54'12.11" | Right | 0.042 | 50 |
| | PI | 223+04.30 | 494931.4155 | 1601041.702 | | | | | | |
| | CC | | 494159.7458 | 1603444.161 | | | | | | |
| | PCC | 224+34.01 | 495052.9169 | 1601087.756 | | | | | | |
| Bethel Curve #13 | PCC | 224+34.01 | 495052.9169 | 1601087.756 | 20000 | 158.46 | 0°27'14.20" | Right | NC | 50 |
| | PI | 225+13.24 | 495127.0022 | 1601115.837 | | | | | | |
| | CC | | 487964.2572 | 1619789.384 | | | | | | |
| | PT | 225+92.47 | 495200.8627 | 1601144.504 | | | | | | |
| Tangent | PT | 225+92.47 | 495200.8627 | 1601144.504 | | | | | | |
| | PC | 229+29.74 | 495515.2859 | 1601266.541 | | | | | | |
| Bethel Curve #14 | PC | 229+29.74 | 495515.2859 | 1601266.541 | 1300 | 417.63 | 18°24'23.02" | Left | 0.067 | 50 |
| | PI | 231+40.37 | 495711.643 | 1601342.753 | | | | | | |
| | CC | | 495985.6652 | 1600054.624 | | | | | | |
| | PT | 233+47.37 | 495922.019 | 1601353.065 | | | | | | |

| Element | Point Type | Station | Northing | Easting | Radius | Length | Delta / Theta | Rotation Direction | Maximum Banking | Design Speed |
|------------------|------------|-----------|-------------|-------------|--------|--------|---------------|--------------------|-----------------|--------------|
| Tangent | PT | 233+47.37 | 495922.019 | 1601353.065 | | | | | | |
| | PC | 237+01.46 | 496275.6867 | 1601370.401 | | | | | | |
| Bethel Curve #15 | PC | 237+01.46 | 496275.6867 | 1601370.401 | 950 | 376.16 | 22°41'12.45" | Right | 0.077 | 50 |
| | PI | 238+92.04 | 496466.0352 | 1601379.731 | | | | | | |
| | CC | | 496229.1759 | 1602319.261 | | | | | | |
| | PT | 240+77.62 | 496638.0573 | 1601461.756 | | | | | | |
| Tangent | PT | 240+77.62 | 496638.0573 | 1601461.756 | | | | | | |
| | PC | 243+53.57 | 496887.1359 | 1601580.523 | | | | | | |
| Bethel Curve #16 | PC | 243+53.57 | 496887.1359 | 1601580.523 | 10000 | 98.3 | 0°33'47.56" | Left | NC | 50 |
| | PI | 244+02.72 | 496931.5005 | 1601601.677 | | | | | | |
| | CC | | 501191.1503 | 1592554.147 | | | | | | |
| | PT | 244+51.87 | 496976.0709 | 1601622.394 | | | | | | |
| Tangent | PT | 244+51.87 | 496976.0709 | 1601622.394 | | | | | | |
| | PC | 247+18.26 | 497217.6435 | 1601734.681 | | | | | | |
| Bethel Curve #17 | PC | 247+18.26 | 497217.6435 | 1601734.681 | 10000 | 90.19 | 0°31'00.25" | Left | NC | 50 |
| | PI | 247+63.36 | 497258.5359 | 1601753.689 | | | | | | |
| | CC | | 501432.723 | 1592666.434 | | | | | | |
| | PT | 248+08.45 | 497299.5981 | 1601772.327 | | | | | | |
| Tangent | PT | 248+08.45 | 497299.5981 | 1601772.327 | | | | | | |
| | PC | 251+98.60 | 497654.8692 | 1601933.583 | | | | | | |
| | | | | | | | | | | |