STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SUMMARY SHEET 5

BEGIN STATION	END STATION	POS.	203.15 COMMON EXCAV.	203.30 EARTH BORROW	204.22 TRENCH EXCAV. OF EARTH, EXP. (N.A.B.I.)	301.28 SUBBASE OF CRUSHED GRAVEL	402.13 AGG. SHOULD. RAP	604.40 CHANGE ELEV. OF D.I., CB OR MANHOLE	604.412 REHAB. D.I. CLASS I	604.415 REHAB. D.I. CLASS II	604.42 CHANGE ELEV. SEWER MANHOLE	616.21 VERTICAL GRANITE CURB	616.28 C.I.P. CONC. CURB	616.40 REMOVE AND RESET CURB	616.41 REMOVAL OF EXIST. CURB	618.10 P.C.C. SIDE-WALK, 5 INCH	618.30 DETECT. WARNING SURFACE	621.20 STEEL BEAM G.R., GALV.	621.60 ANCHOR FOR S.B. GUARDRAIL	621.80 REMOVAL & DISP. OF G.R.	629.20 ADJUST ELEV. OF VALVE BOX	651.35 TOPSOIL	676.10 DELINE. WITH STEEL POSTS	676.12 REMOVAL OF EXIST. DELINE.	REMARKS
			CY	CY	CY	TON	TON	EA	EA	EA	EA	LF	LF	LF	LF	SY	SF	LF	EA	LF	EA	CY	EA	EA	
NORTHFIELD ROUTE 12A							62														1				
NORTHFIELD ROUTE 12							74	2	52	13	25										63				
177+93	177+99	LT	1.0			0.9										3.2	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 2 FROM STANDARD DRAWING C-3A
189+98	190+05	LT	1.2			1.1										3.9	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
190+00	190+05	RT	0.9			0.8										2.9	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
190+41	190+57	LT	0.9			0.8								15		3.0	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
192+41	192+59	LT	1.0			0.9								15		3.2	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
192+91	193+06	LT	0.8			0.7								15		2.6	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
194+80	194+98	RT	0.9			0.8								15		3.0	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
199+45	199+61	RT	0.9			0.8								15		2.9	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
199+97	200+15	RT	1.1			0.9								16		3.4	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
200+70	200+86	RT	0.9			0.8								16		3.0	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 6,
																									EXAMPLE 5 FROM STANDARD DRAWING C-3B
200+72	200+87	LT	0.8			0.7								15		2.6	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
201+08	201+23	LT	0.8			0.7								15		2.6	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
204+64	204+80	LT	0.8			0.7								16		2.7	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
204+98	205+14	LT	0.8			0.8								15		2.8	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
208+53	208+79	LT	0.8			0.7								15		2.6	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 6,
																									EXAMPLE 5 FROM STANDARD DRAWING C-3B
208+55	208+70	RT	0.8			0.7								25		2.7	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
209+05	209+21	RT	0.7			0.7								14		2.4	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
211+70	211+83	RT	0.5			0.5								15		1.7	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
212+12	212+30	RT	0.9			0.8								15		3.0	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
214+85	215+02	RT	0.9			0.8								15		2.9	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
215+36	215+53	RT	0.9			0.8								15		2.9	8								CONSTRUCT NEW SIDEWALK RAMP TYPE 1,
																									EXAMPLE 1 FROM STANDARD DRAWING C-3A
SUBTOTAL			18.3	-	-	16.4	136	2	52	13	25	-	-	282	-	60.0	168	-	-	-	64	-	-	-	

ITEM DETAIL SUMMARY SHEET 5

PROJECT NAME: BETHEL - RANDOLPH - NORTHFIELD
PROJECT NUMBER: STP 2922 (I)

FILE NAME: p10C246.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p10C246_17.i

PLOT DATE: 1/3/13
DRAWN BY: JBG
CHECKED BY: CDL
SHEET 17 OF 149