STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 40

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGNS AND MARKINGS	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. 169+00 LT NORTHFIELD VT ROUTE 12	Randolph 16	1	72	12	6.00						2												X		450									VDI-IA		136	
	Bethel 24	1	72	12	6.00																													VDI-IA		136	
	Roxbury 7	1	72	12	6.00																													VDI-IA		136	
	Randolph 21	1	72	12	6.00																													VDI-IA		136	
	SOUTH TO SOUTH	1	24	12	2.00																													M3-3 GREEN ON WHITE	SHSM		
	VERMONT 12 INTERSTATE 89 VERMONT 12A	1	24	12	2.00																													M4-5 WHITE ON BLUE	SHSM		
		1	24	12	2.00																												#3A	M3-3 GREEN ON WHITE	SHSM		
		1	24	24	4.00																													M1-5 GREEN ON WHITE			E-136B
		1	24	24	4.00																													M1-1 WHITE ON BLUE	SHSM		
		1	30	24	5.00																													M1-5 GREEN ON WHITE			E-136B
		1	21	15	2.19																													M6-3 GREEN ON WHITE	SHSM		
		1	21	15	2.19																													M6-3 WHITE ON BLUE	SHSM		
		1	21	15	2.19																													M6-IR GREEN ON WHITE	SHSM		
STA. 170+20 RT NORTHFIELD VT ROUTE 12		1	30	30	6.25						1					X			X														WII-2 FLUORESCENT YELLOW-GREEN, TYPE IX SHEETING	SHSM		
	AHEAD	1	24	12	2.00																													WI6-9P FLUORESCENT YELLOW-GREEN, TYPE IX SHEETING	SHSM		
STA. 170+25 LT NORTHFIELD VT ROUTE 12	STOP	1	30	30	6.25						1					X			X														RI-1	SHSM		
~~STA. 170+25 LT NORTHFIELD VT ROUTE 12~~	DO NOT ENTER	1	30	30	6.25						1					X			X														R5-1	SHSM		
STA. 170+61 LT NORTHFIELD VT ROUTE 12	Park Av	1	24	12	2.00						1					X			X														D3-1		138	
	STOP	1	30	30	6.25																													RI-1	SHSM		
												LF	LF	LF	LF -	LF 60	LF -		EA.	LB	LB	LB		LB	LB 450	LB	LB									
TOTALS					SF 78.57	SF	EA. -	SF				LF			LF 60					LB			EA. 2	LB 450				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 40

PROJECT NAME: BETHEL - RANDOLPH - NORTHFIELD
PROJECT NUMBER: STP 2922 (1)

FILE NAME: p10C246.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p10C246_114.i

PLOT DATE: 1/3/13
DRAWN BY: JBG
CHECKED BY: CDL
SHEET 114 OF 149