STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 58

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) lb/ft FOUND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGNS AND MARKINGS	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. 255+50 LT NORTHFIELD VT ROUTE 12	STATE HIGHWAY ENDS	1	24	18	3.00						1					X		X														VR-038			E-141
	SPEED LIMIT 30	1	24	30	5.00																											R2-1	SHSM		
STA. 255+50 RT NORTHFIELD VT ROUTE 12	STATE HIGHWAY BEGINS	1	24	18	3.00						1					X		X														VR-039			E-141
	~~SPEED LIMIT 30~~ SPEED LIMIT 35	1	24	30	5.00																											INSTALLED SPEED LIMIT 35 MPH SIGN R2-1 REMOVED SPEED LIMIT 35 MPH SIGN	SHSM		
STA. 255+50 LT NORTHFIELD VT ROUTE 12	0120 1213 XXXX																																			
	SUBTOTAL THIS SHEET				16.00		-								-	30							-	-												
	TSS SHEET 1 TOTAL				51.49		-								-	30	15						2	304												
	TSS SHEET 2 TOTAL				45.11		-								-	105	-						-	-												
	TSS SHEET 3 TOTAL				38.59		-								-	90	-						-	-												
	TSS SHEET 4 TOTAL				32.63		-								-	75	-						-	-												
	TSS SHEET 5 TOTAL				42.44		-								-	90	-						-	-												
	TSS SHEET 6 TOTAL				29.40		1								-	90	-						-	-												
	TSS SHEET 7 TOTAL				34.30		-								-	60	-						-	-												
	TSS SHEET 8 TOTAL				24.75		-								-	45	-						-	-												
	TSS SHEET 9 TOTAL				41.33		1								-	75	15						-	-												
	TSS SHEET 10 TOTAL				40.94		-								-	90	-						-	-												
	TSS SHEET 11 TOTAL				38.34		-								-	90	-						-	-												
	TSS SHEET 12 TOTAL				42.04		-								-	105	-						-	-												
	TSS SHEET 13 TOTAL				48.08		-								-	90	-						-	-												
	TSS SHEET 14 TOTAL				40.50		2								-	75	-						-	-												
	TSS SHEET 15 TOTAL				34.85		2								-	75	-						-	-												
												LF	LF	LF	LF	LF	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
															-	1185	30																			
	TOTALS				SF 584.79	SF	EA. 6	SF				LF			LF 1215					LB			EA. 2	LB 304				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 58

PROJECT NAME: BETHEL - RANDOLPH - NORTHFIELD
PROJECT NUMBER: STP 2922 (1)

FILE NAME: p10C246.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p10C246_132.i

PLOT DATE: 1/3/13
DRAWN BY: JBG
CHECKED BY: CDL
SHEET 132 OF 149