

STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET 4

BEGIN STATION	END STATION	POS.	203.16 SOLID ROCK EXCAV.	203.30 EARTH BORROW	204.22 TRENCH EXCAV. OF EARTH, EXP. (N.A.B.I.)	402.13 AGG. SHOULDER RAP	525.50 BRIDGE RAIL REPAIR, TYPE I	613.10 STONE FILL, TYPE I	619.17 YIELDING MARKER POSTS	621.20 STEEL BEAM G.R. GALV	621.206 STEEL BEAM G.R. GALV NESTED	621.21 HD STEEL BEAM G.R. GALV	621.60 ANCHOR FOR S.B. GUARDRAIL	621.75 REMOVE & RESET G.R.	621.80 REMOVE & DISP. OF G.R.	649.51 GEOT. FOR SILT FENCE	651.35 TOPSOIL	651.40 GRUBBING MATERIAL (2")	653.20 GRUBBING MATERIAL (6")	653.20 TEMP. EROSION MATTING	676.10 TYPE I GUARD RAIL ENDS	676.10 TYPE II	676.12 REMOVAL OF EXIST. DELINE.	900.640 SPEC. PRO. (BOX BEAM G.R. W/7 FEET POSTS)	REMARKS
			CY	CY	CY	TON	LF	CY	EACH	LF	LF	LF	EACH	LF	LF	SY	CY	SY	SY	SY	EACH		EACH	LF	
358+40	359+40	RT						17.0								44.4			34.4	34.4					PLACE STONE ON SLOPES GREATER THAN 1:1.5 FOR SLOPE STABILIZATION
367+59.5	371+13.5	RT		50													10				2			354	SEE VTRANS STANDARD G-1BM FOR END SECTION DETAILS
368+90	369+30	RT						13.5								17.8			33.8	33.8					PLACE STONE ON SLOPES GREATER THAN 1:1.5 FOR SLOPE STABILIZATION
369+70	370+60	RT						22.1								40			51.3	51.3					PLACE STONE ON SLOPES GREATER THAN 1:1.5 FOR SLOPE STABILIZATION
373+00	374+00	RT						34.8								44.4			87.6	87.6					PLACE STONE ON SLOPES GREATER THAN 1:1.5 FOR SLOPE STABILIZATION
381+69	382+42	LT																				5			INSTALL TYPE II DELINIATOR ALONG PAVEMENT REMOVAL AREA
SUBTOTAL SHEET 21			61.9	400	1	710.7	-	252.1	72	-	-	-	-	-	5724	487.7	211.0	14977.8	263	263	16	-	16	6060	
SUBTOTAL SHEET 22			-	400	-	-	-	171.6	-	37.5	87.5	-	2	-	1017	317.7	80	-	396.3	396.3	14	-	12	1638	
SUBTOTAL SHEET 23			-	350	-	-	50	241.1	-	112.5	-	82.5	4	268	2733	464.4	70	-	549	549	14	-	12	5190	
SUBTOTAL SHEET 24			-	50	-	-	-	87.4	-	-	-	-	-	-	-	146.6	10	-	207.1	207.1	2	5	-	354	
ROUNDING			-	-	-	39.3	-	-	-	-	-	-	-	32	26	33.6	-	422.2	24.6	-	-	-	-	6	
TOTAL			61.9	1200	1	750	50	752.2	72	150	87.5	82.5	6	300	9500	1450	371	15400	1440	1415.4	46	5	40	13248	

PROJECT NAME: HANCOCK
PROJECT NUMBER: STP 2923 (1)
FILE NAME: z10c252ids.dgn PLOT DATE: 3/18/2015
PROJECT LEADER: C. LATHROP DRAWN BY: J. GOODALL
DESIGNED BY: B. MARTIN CHECKED BY: C. LATHROP
ITEM DETAIL SHEET 4 SHEET 24 OF 207