

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Direction	Maximum Banking	Design Speed
Tangent	POB	41+24.00	525270.807	1521025.227						
	PC	44+22.55	525204.627	1521316.349						
Curve #1	PC	44+22.55	525204.627	1521316.349	360	445.31	70°52'23.33"	Right	0.080	35
	PI	46+78.73	525147.838	1521566.16						
	CC		524853.583	1521236.547						
	PT	48+67.86	524893.21	1521594.36						
Tangent	PT	48+67.86	524893.21	1521594.36						
	PC	51+97.28	524565.788	1521630.621						
Curve #2	PC	51+97.28	524565.788	1521630.621	700	305.66	25°01'07.58"	Left	0.080	45
	PI	53+52.59	524411.425	1521647.716						
	CC		524642.84	1522326.367						
	PT	55+02.94	524278.776	1521728.49						
Tangent	PT	55+02.94	524278.776	1521728.49						
	PC	55+92.42	524202.358	1521775.023						
Curve #3	PC	55+92.42	524202.358	1521775.023	1125	239.11	12°10'39.27"	Left	0.072	50
	PI	57+12.42	524099.86	1521837.437						
	CC		524787.461	1522735.898						
	PT	58+31.52	524012.834	1521920.067						
Tangent	PT	58+31.52	524012.834	1521920.067						
	PC	59+73.57	523909.825	1522017.874						
Curve #4	PC	59+73.57	523909.825	1522017.874	480	277.8	33°09'36.71"	Right	0.080	40
	PI	61+16.48	523806.188	1522116.277						
	CC		523579.318	1521669.786						
	PT	62+51.37	523665.603	1522141.967						
Tangent	PT	62+51.37	523665.603	1522141.967						
	PC	63+89.45	523529.768	1522166.789						
Curve #5	PC	63+89.45	523529.768	1522166.789	5000	72.71	0°49'59.47"	Right	0.024	50
	PI	64+25.81	523494.005	1522173.324						
	CC		522630.97	1517248.236						
	PT	64+62.16	523458.151	1522179.339						
Tangent	PT	64+62.16	523458.151	1522179.339						
	PC	67+49.21	523175.058	1522226.827						
Curve #6	PC	67+49.21	523175.058	1522226.827	375	284.25	43°25'49.91"	Left	0.080	35
	PI	68+98.56	523027.769	1522251.534						
	CC		523237.096	1522596.66						
	PT	70+33.46	522937.793	1522370.734						
Tangent	PT	70+33.46	522937.793	1522370.734						
	PC	71+27.81	522880.949	1522446.04						
Curve #7	PC	71+27.81	522880.949	1522446.04	700	479.61	39°15'24.88"	Right	0.080	45
	PI	73+77.47	522730.542	1522645.296						
	CC		522322.249	1522024.312						
	PT	76+07.43	522487.991	1522704.407						
Tangent	PT	76+07.43	522487.991	1522704.407						
	PC	77+74.97	522325.217	1522744.075						
Curve #8	PC	77+74.97	522325.217	1522744.075	800	284.52	20°22'39.09"	Right	0.079	50
	PI	79+18.75	522185.525	1522778.119						
	CC		522135.798	1521966.824						
	PT	80+59.49	522042.721	1522761.39						
Tangent	PT	80+59.49	522042.721	1522761.39						
	PC	83+09.14	521794.77	1522732.345						
Curve #9	PC	83+09.14	521794.77	1522732.345	500	299.08	34°16'19.31"	Left	0.080	40
	PI	84+63.30	521641.653	1522714.408						
	CC		521736.596	1523228.949						
	PT	86+08.22	521505.02	1522785.81						
Tangent	PT	86+08.22	521505.02	1522785.81						
	PC	95+95.01	520630.447	1523242.845						
Curve #10	PC	95+95.01	520630.447	1523242.845	1115	814.36	41°50'49.06"	Left	0.072	50
	PI	100+21.31	520252.626	1523440.287						
	CC		521146.862	1524231.046						
	PT	104+09.37	520102.898	1523839.428						

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Direction	Maximum Banking	Design Speed
Tangent	PT	104+09.37	520102.898	1523839.428						
	PC	104+56.37	520086.39	1523883.435						
Curve #11	PC	104+56.37	520086.39	1523883.435	1110	601.74	31°03'37.93"	Left	0.072	50
	PI	107+64.83	519978.05	1524172.245						
	CC		521125.672	1524273.296						
	PT	110+58.11	520034.253	1524475.543						
Tangent	PT	110+58.11	520034.253	1524475.543						
	PC	111+55.57	520052.01	1524571.37						
Curve #12	PC	111+55.57	520052.01	1524571.37	910	445.47	28°02'52.99"	Right	0.078	50
	PI	113+82.86	520093.424	1524794.859						
	CC		519157.243	1524737.176						
	PT	116+01.04	520024.887	1525011.574						
Tangent	PT	116+01.04	520024.887	1525011.574						
	PC	120+39.66	519892.628	1525429.778						
Curve #13	PC	120+39.66	519892.628	1525429.778	1200	390.25	18°37'58.41"	Left	0.070	50
	PI	122+36.52	519833.267	1525617.476						
	CC		521036.774	1525791.62						
	PT	124+29.91	519836.988	1525814.302						
Tangent	PT	124+29.91	519836.988	1525814.302						
	PC	125+90.50	519840.024	1525974.864						
Curve #14	PC	125+90.50	519840.024	1525974.864	1100	552.05	28°45'16.88"	Left	0.072	50
	PI	128+72.47	519845.353	1526256.782						
	CC		520939.827	1525954.072						
	PCC	131+42.55	519985.645	1526501.372						
Curve #14	PCC	131+42.55	519985.645	1526501.372	2999.14	387.57	7°24'15.23"	Left	0.037	50
	PI	133+36.60	520082.197	1526669.704						
	CC		522587.215	1525009.164						
	PT	135+30.12	520199.637	1526824.191						
Tangent	PT	135+30.12	520199.637	1526824.191						
	PC	136+23.55	520256.179	1526898.569						
Curve #15	PC	136+23.55	520256.179	1526898.569	700	531.3	43°29'14.60"	Right	0.080	45
	PI	139+02.73	520425.135	1527120.822						
	CC		519698.918	1527322.196						
	PT	141+54.85	520394.764	1527398.348						
Tangent	PT	141+54.85	520394.764	1527398.348						
	PC	143+37.20	520374.927	1527579.612						
Curve #16	PC	143+37.20	520374.927	1527579.612	1200	329.37	15°43'34.92"	Left	0.070	50
	PI	145+02.92	520356.898	1527744.356						
	CC		521567.805	1527710.157						
	PT	146+66.57	520384.196	1527907.82						
Tangent	PT	146+66.57	520384.196	1527907.82						
	PC	148+17.98	520409.136	1528057.16						
Curve #17	PC	148+17.98	520409.136	1528057.16	900	258.67	16°28'03.94"	Right	0.078	50
	PI	149+48.21	520430.588	1528185.617						
	CC		519521.43	1528205.408						
	PT	150+76.65	520414.746	1528314.885						
Tangent	PT	150+76.65	520414.746	1528314.885						
	PC	154+41.55	520370.36	1528677.073						
Curve #18	PC	154+41.55	520370.36	1528677.073	3000	285.49	5°27'08.71"	Left	0.037	50
	PI	155+84.40	520352.983	1528818.864						
	CC		523348.082	1529041.996						
	PT	157+27.04	520349.158	1528961.665						
Tangent	PT	157+27.04	520349.158	1528961.665						
	PC	158+59.86	520345.601	1529094.44						
Curve #19	PC	158+59.86	520345.601	1529094.44	600	269	25°41'14.25"	Left	0.080	45
	PI	159+96.66	520341.938	1529231.188						
	CC		520945.386	1529110.506						
	PT	161+28.86	520397.912	1529356.01						
Tangent	PT	161+28.86	520397.912	1529356.01						
	PC	164+23.49	520518.469	1529624.852						

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Direction	Maximum Banking	Design Speed
Curve #20	PC	164+23.49	520518.469	1529624.852	775	485.34	35°52'51.95"	Right	0.080	50
	PI	166+74.42	520621.14	1529853.81						
	CC		519811.315	1529941.961						
	PT	169+08.83	520570.135	1530099.495						
Tangent	PT	169+08.83	520570.135	1530099.495						
	PC	171+19.24	520527.366	1530305.509						
Curve #21	PC	171+19.24	520527.366	1530305.509	5000	52.6	0°36'09.77"	Left	0.024	50
	PI	171+45.54	520522.02	1530331.258						
	CC		525422.98	1531321.856						
	PT	171+71.83	520516.946	1530357.063						
Tangent	PT	171+71.83	520516.946	1530357.063						
	PC	175+22.97	520449.19	1530701.604						
Curve #22	PC	175+22.97	520449.19	1530701.604	10000	86.72	0°29'48.65"	Right	NC	50
	PI	175+66.33	520440.824	1530744.147						
	CC		510637.121	1530772.017						
	PT	176+09.69	520432.089	1530786.617						
Tangent	PT	176+09.69	520432.089	1530786.617						
	PC	17								