STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 14

MILE MARKER, STATION OR SIGN NUMBER		SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																					REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL	
											NO. OF POST	SQUARE STEEL (in)						TUBULAR STEEL Ø (IN)					W-SHAPE STEEL										
		EACH	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	ANCHOR	SLEEVE				FOUND-ATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60	FTG. SIZE 24"	FTG. SIZE 30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED		DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
OPTION ITEMS																																
STA. 379+81 LT		1	30	15	3.13																										VM-064 GREEN ON WHITE	123	
		1	30	24	5.00																										M1-5 GREEN ON WHITE		E-136B
		1	6	10	0.42																										VD-700		T-44
STA. 380+00 LT		1	24	30	5.00						1			15		X														R2-1		SHSM
STA. 382+03 RT		1	36	36	9.00						2			30		X														R1-1		SHSM
		1	6	10	0.42																										VD-700		T-44
	TSSS 1 TOTAL				41.00		-							0	150						-	-										
	TSSS 2 TOTAL				40.42		-							8	60						-	-										
	TSSS 3 TOTAL				38.67		-							0	75						-	-										
	TSSS 4 TOTAL				32.34		-							16	120						-	-										
	TSSS 5 TOTAL				18.94		-							56	60						-	-										
	TSSS 6 TOTAL				3.36		-							64	0						-	-										
	TSSS 7 TOTAL				13.35		-							32	30						-	-										
	TSSS 8 TOTAL				18.77		-							48	45						-	-										
	TSSS 9 TOTAL				14.10		-							40	60						-	-										
	TSSS 10 TOTAL				16.68		3							32	45						-	-										
	TSSS 11 TOTAL				30.67		3							8	105						-	-										
	TSSS 12 TOTAL				47.49		-							8	120						-	-										
	TSSS 13 TOTAL				46.38		-							0	15						2	289										
	TSSS 14 TOTAL				22.97		-							0	45						-	-										
				SUBTOTAL	385.14									FT 312	FT 930	FT		EA			EA. 2	LB 289	LB	LB	LB	LB							
				ROUNDING	4.86																												
				TOTALS	SF 390.0	SF	EA. 6.	SF				FT		FT 1242			LB		EA. 2	LB 295				EA.	EA.	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HANCOCK
PROJECT NUMBER: STP 2923 (1)

FILE NAME: z10c252tsss.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: B. MARTIN
TRAFFIC SIGN SUMMARY SHEET 14

PLOT DATE: 3/18/2015
DRAWN BY: J. GOODALL
CHECKED BY: C. LATHROP
SHEET 122 OF 207