ITEM DETAIL SUMMARY SHEET 5

LOCATION			GUARDRAIL							MISCELLANEOUS											REMARKS
BEGIN MILE STA.	END MILE STA.	POS.	621.20 S.B. G.R. GALV. LF	621.205 S.B. G.R. GALV.W/ 8' POST LF	621.21 HD S.B. G.R. GALV. LF	621.216 HD S.B. G.R., GALV./ NESTED LF	621.53 TERMINAL CONN. FOR S.B. G.R. EACH	621.60 ANCHOR FOR S.B. RAIL EACH	621.80 REMOVAL & DISPOSAL OF GUARDRAIL LF	203.15 COMMON EXCAVATION CY	203.30 EARTH BORROW CY	301.28 SUBBASE OF CRUSHED GRAV, FINE GRADED TON	402.13 AGGREGATE SHOULDERS, RAP TON	601.2615 18" CPEP(SL) LF	604.412 REHAB DI, CB, OR MH, CLASS I EACH	604.415 REHAB DI, CB, OR MH, CLASS II EACH	604.42 CHAN ELEV. OF SEWER MH EACH	613.10 STONE FILL, TYPE I CY	616.28 C-I-P CONC. CURB, TYPE B LF	616.35 TREATED TIMBER CURB LF	
US ROUTE 5																					
LYNDON																					
90+38		RT								1.6		1.6									CONSTRUCT SIDEWALK RAMP, TYPE 1.
124+17.5	125+19	LT	79			25		2	100		50										INSTALL ANCHOR @ STA. 124+18 AND 125+19; SEE CULVERT SPAN DETAIL ON SHEET 17.
ST. JOHNSBURY STATE HIGHWAY																					
ST. JOHNSBURY																					
2+18	3+81	RT	139.5				1	1	162.5		25									63	INSTALL ANCHOR @ STA. 2+18. CONNECT GUARDRAIL TO PERMANENT JERSEY BARRIER @ STA. 3+81. REFER TO SHEET 19. INSTALL TREATED TIMBER CURB STA. 3+18 TO 3+81.
2+45	3+94.5	LT	127				1	1	150		25									80	INSTALL ANCHOR @ STA. 2+45. CONNECT GUARDRAIL TO PERMANENT JERSEY BARRIER @ STA. 3+94.5 REFER TO SHEET 19. INSTALL TREATED TIMBER CURB STA. 3+14.5 TO 3+94.5.
8+08	9+71	RT	139.5				1	1	162.5		25										CONNECT GUARDRAIL TO PERMANENT JERSEY BARRIER @ STA. 8+08. SEE SHEET 19. INSTALL ANCHOR @ STA. 9+71.
8+24.5	10+22.5	LT	177				1	1	200		25										CONNECT GUARDRAIL TO PERMANENT JERSEY BARRIER @ STA. 8+24.5. SEE SHEET 19. INSTALL ANCHOR @ STA. 10+22.5.
22+09.5	26+16.5	RT	416.5					2	412.5		50										INSTALL ANCHOR @ STA. 22+09.5 AND 26+16.5
SHEET 9 SUBTOTALS:			7440		82.5		4	26	7487.5	6.6	650	6.4	1323	75	35	9	16	398	12		
SHEET 11 SUBTOTALS:			5661	154	108.75	25	4	30	5910	18.5	750	5.6		225				22		407	
SHEET 13 SUBTOTALS:			1078.5			25	4	8	1187.5	1.6	200	1.6								143	
SUBTOTALS:			14179.5	154	191.25	50	12	64	14585	26.7	1600	13.6	1323	300	35	9	16	420	12	550	
ROUNDING			20.5	21	8.75	-	-	-	15	3.3	-	1.4	27	-	-	-	-	5	1	10	
TOTALS			14200	175	200	50	12	64	14600	30	1600	15	1350	300	35	9	16	425	13	560	

ITEM DETAIL SUMMARY SHEET #5

PROJECT NAME: ST. JOHNSBURY-LYNDON
PROJECT NUMBER: STP 2928(I)

FILE NAME: p10c262.dgn
PROJECT LEADER: JLL
DESIGNED BY: MCF
IPARM FILE: p10c262idss05.i

PLOT DATE: 10/17/2013
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 13 OF 133