ITEM DETAIL SUMMARY SHEET 6

LOCATION			MISCELLANEOUS															REMARKS
BEGIN MILE STA.	END MILE STA.	POS.	616.40 REMOVING & RESETTING CURB LF	616.41 REMOVAL OF EXISTING CURB LF	616.47 BIT. CONC. GUTTERS & TRAFF. ISL. TON	617.10 RELOCATE MAILBOX, SINGLE SUPPORT EACH	617.12 RELOCATE MAILBOX, MULTIPLE SUPPORT EACH	618.10 PORTLAND CEMENT CONC., 5 INCH SY	618.30 DETECTABLE WARNING SURFACE SF	619.17 YIELDING MARKER POSTS EACH	629.20 ADJUST ELEV VALVE BOX EACH	649.31 GEOTEXTILE UNDER STONE FILL SY	651.40 GRUBBING MATERIAL SY	653.20 TEMPORARY EROSION MATTING SY	676.10 DELINEATOR WITH STEEL POST EACH	676.12 REMOVAL OF EXIST. DELINEATOR EA			
US ROTUE 5																		
LYNDON																		
90+38		RT	12					5	8									CONSTRUCT SIDEWALK RAMP, TYPE 1.
124+17.5	125+19	LT												50	2	2		INSTALL ANCHOR @ STA. 124+18 AND 125+19; SEE CULVERT SPAN DETAIL ON SHEET 17.
ST. JOHNSBURY STATE HIGHWAY																		
ST. JOHNSBURY																		
2+18	3+81	RT												25	1	1		INSTALL ANCHOR @ STA. 2+18. CONNECT GUARDRAIL TO PERMANENT JERSEY BARRIER @ STA. 3+81. REFER TO SHEET 19. INSTALL TREATED TIMBER CURB STA. 3+18 TO 3+81.
2+45	3+94.5	LT												25	1	1		INSTALL ANCHOR @ STA. 2+45. CONNECT GUARDRAIL TO PERMANENT JERSEY BARRIER @ STA. 3+94.5 REFER TO SHEET 19. INSTALL TREATED TIMBER CURB STA. 3+14.5 TO 3+94.5.
8+08	9+71	RT												25	1	1		CONNECT GUARDRAIL TO PERMANENT JERSEY BARRIER @ STA. 8+08. SEE SHEET 19. INSTALL ANCHOR @ STA. 9+71.
8+24.5	10+22.5	LT												25	1	1		CONNECT GUARDRAIL TO PERMANENT JERSEY BARRIER @ STA. 8+24.5. SEE SHEET 19. INSTALL ANCHOR @ STA. 10+22.5.
22+09.5	26+16.5	RT												50	2	2		INSTALL ANCHOR @ STA. 22+09.5 AND 26+16.5
SHEET 10 SUBTOTALS:				12	4.0	2	1	22	42	106	20	1642	349	2966	26	22		
SHEET 12 SUBTOTALS:					28.8			19	24			79	53	919	30	27		
SHEET 14 SUBTOTALS:			12					5	8					200	8	8		
SUBTOTALS:			12	12	32.8	2	1	46	74	106	20	1721	402	4085	64	57		
ROUNDING			1	1	2.2	-	-	4	6	-	-	29	8	15	1	1		
TOTALS			13	13	35	2	1	50	80	106	20	1750	410	4100	65	58		

ITEM DETAIL SUMMARY SHEET #6

PROJECT NAME: ST. JOHNSBURY-LYNDON
PROJECT NUMBER: STP 2928(I)

FILE NAME: p10c262.dgn
PROJECT LEADER: JLL
DESIGNED BY: MCF
IPARM FILE: p10c262idss06.i

PLOT DATE: 10/17/2013
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 14 OF 133