

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY US 5	ROADWAY US 5 (NO FED /STATE PART.)	TRAINING	RAILROAD - BID ITEMS	BRIDGE NO. 109	BRIDGE	FULL C.E. ITEMS	ROADWAY NEWBURY SH	ROADWAY US 302	ROADWAY US 302 (NO FED /STATE PART.)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
801							27	22		850		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
20										20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE II (PNEUMATIC HAMMER)	608.26	EST.			
90							5	5		100		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
190								10		200		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
1650							55	45		1750		HR	TRUCK RENTAL	608.37	EST.			
80							10	10		100		HR	LOADER RENTAL, TYPE I	608.40	EST.			
685										685		CY	STONE FILL, TYPE I	613.10	8			
185										185		LF	VERTICAL GRANITE CURB	616.21	5.5			
95										95		LF	TREATED TIMBER CURB	616.35	-			
110										110		LF	REMOVAL OF EXISTING CURB	616.41	5			
90							1			91		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	0.7			
290										290		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	5.1			
270										270		SF	DETECTABLE WARNING SURFACE	618.30	2			
40							10			50		EACH	YIELDING MARKER POSTS	619.17	EST.			
18075							100	275		18450		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	172.5			
2850										2850		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	32.5			
25								75		100		LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.206	-			
50										50		LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.207	-			
2										2		EACH	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53	-			
118							2	3		123		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
								1		1		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM	621.72	-			
8										8		EACH	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM	621.737	-			
26925							175			27100		LF	REMOVE AND RESET GUARDRAIL	621.75	95.5			
150										150		EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76	-			
75										75		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77	-			
20725							100	375		21200		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	186			
							60			60		LF	TEMPORARY TRAFFIC BARRIER	621.90	-			
	7									7		EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-			
3050							100	75		3225		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
12200							375	250		12825		HR	FLAGGERS	630.15	EST.			
						1				1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
						1				1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
						1				1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
						3000				3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
	520									520		HR	EMPLOYEE TRAINEESHIP	634.10	-			
							1			1		LS	MOBILIZATION/DEMobilIZATION (NEWBURY STATE HIGHWAY)	635.11	-			
								1		1		LS	MOBILIZATION/DEMobilIZATION (US 302)	635.11	-			
1										1		LS	MOBILIZATION/DEMobilIZATION (US 5)	635.11	-			
							1			1		LS	TRAFFIC CONTROL (NEWBURY STATE HIGHWAY)	641.10	-			
								1		1		LS	TRAFFIC CONTROL (US 302)	641.10	-			

PROJECT NAME: BRADFORD-RYEGATE  
 PROJECT NUMBER: STP 2929(I)  
 FILE NAME: z10c264frm.dgn  
 PROJECT LEADER: P. SHEDD  
 DESIGNED BY: N. LEMAY  
 QUANTITY SHEET 2  
 PLOT DATE: 2/4/2016  
 DRAWN BY: W. GORDON  
 CHECKED BY: P. SHEDD  
 SHEET 16 OF 239