LOCATION			DROP INLETS			CURB			SIDEWALK		MISC.											REMARKS
			604.412	604.415	604.418	541.30	616.21	616.35	618.10	618.30	613.10	653.20										
STA	STA	POS	REHAB. DI, CB, OR MH, CLASS I	REHAB. DI, CB, OR MH, CLASS II	REHAB. DI, CB, OR MH, CLASS III	CONCRETE, CLASS C	VERTICAL GRANITE CURB	TREATED TIMBER CURB	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	DETECT. WARNING SURFACE (DWS)	STONE FILL, TYPE I	TEMP. EROSION MATTING										
			EACH	EACH	EACH	CY	LF	LF	SY	SF	CY	SY										
	RYEGATE																					
	US ROUTE 5																					
R 5+31	R 5+56	RT									3											SEE SHOULDER STABILIZATION DETAIL ON DETAIL SHEET 2
R 5+40	R 5+60	LT									5	9.0										SEE FILL SLOPE WITH STONE FILL DETAIL ON DETAIL SHEET 2
	NEWBURY STATE HWY																					
0+21	24+49	LT/RT	2	1																		ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
0+21	24+49	LT/RT										50.0										ESTIMATED QUANTITY TO BE USED AT GUARDRAIL END TERMINALS
0+21	24+49	LT/RT										88.0										FOR PROJECT SUBTOTAL SEE DITCH CLEANING SHEET
	US ROUTE 302																					
M 242+50	M 244+75	LT/RT	7	1								75.0										ESTIMATED QUANTITY TO BE USED AT GUARDRAIL END TERMINALS
SUBTOTAL SHEET 27			70	9	9	0.7	138.0	0.0	156.0	128	180	7698.0										
SUBTOTAL SHEET 28			0	0	0	0.5	41.5	95.0	128.9	140	489	1201.0										
SUBTOTAL SHEET 29			9	2	0	0.0	0.0	0.0	0.0	0	8	222.0										
PROJECT SUBTOTAL			79	11	9	1.2	179.5	95.0	284.9	268	677	9121.0										
TOTAL ROUNDING			0	0	0	0.3	5.5	0.0	5.1	2	8	79.0										
PROJECT TOTAL			79	11	9	1.5	185.0	95.0	290.0	270	685	9200.0										

CLD 14-0278

PROJECT NAME: BRADFORD-RYEGATE
PROJECT NUMBER: STP 2929(I)

FILE NAME: z10c264frm.dgn
PROJECT LEADER: P. SHEDD
DESIGNED BY: N. LEMAY
ITEM DETAIL SHEET 10

PLOT DATE: 2/4/2016
DRAWN BY: W. GORDON
CHECKED BY: P. SHEDD
SHEET 29 OF 239