QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

GOV'T NON PARTIC.	TRAINING	FULL CE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			2	2	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
			2	2	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-
10				10	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
			17600	17600	LF	6 INCH UNDERDRAIN PIPE	605.10	259
			60	60	HR	POWER GRADER RENTAL	608.15	EST.
			380	380	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
			40	40	HR	POWER BROOM RENTAL,TYPE I	608.30	EST.
			760	760	HR	TRUCK RENTAL	608.37	EST.
			40	40	HR	LOADER RENTAL, TYPE I	608.40	EST.
			6150	6150	CY	STONE FILL, TYPE I	613.10	95.5
			160	160	LF	REMOVAL OF EXISTING CURB	616.41	1
			13	13	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-
			1	1	EA	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12	EST.
			271	271	EA	YIELDING MARKER POSTS	619.17	EST.
			220	220	LF	REMOVING AND RESETTING FENCE	620.50	5
			4900	4900	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	20.25
			450	450	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	21
			25	25	LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.206	-
			25	25	LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.207	-
			20	20	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
			7170	7170	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	33
			1	1	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
			1100	1100	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			10800	10800	HR	FLAGGERS	630.15	EST.
		1		1	LS	FIELD OFFICE, ENGINEERS	631.10	-
		1		1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
		1		1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
		3000		3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
	520			520	HR	EMPLOYEE TRAINEESHIP	634.10	-
			1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1	1	LS	TRAFFIC CONTROL	641.10	-
			2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						BEGIN OPTION AA		
			77200	77200	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	740
			77200	77200	LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	740
						END OPTION AA		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		STONE FILL, TYPE I
1855.5	CY	ITEM DETAIL SHEET 3
4199	CY	DITCH CLEANING DETAIL SHEET
95.5	CY	ROUNDING
6150	CY	TOTAL
		YIELDING MARKER POSTS
151	EA	ITEM DETAIL SHEET 3
120	EA	UNDERDRAIN DETAIL SHEET 1
-	EA	ROUNDING
271	EA	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: RANDOLPH
PROJECT NUMBER: STP 2932(1)

FILE NAME: z10c270.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: B. BRESLEND
QUANTITY SHEET 2

PLOT DATE: 6/5/2014
DRAWN BY: J. GOODALL
CHECKED BY: C. LATHROP