QUANTITY SHEET 4

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

GOV'T NON PARTIC.	TRAINING	FULL CE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			43	43	EA	DELINEATOR WITH STEEL POST	676.10	-
			24	24	EA	REMOVAL OF EXISTING DELINEATOR	676.12	-
			1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
			3	3	EA	SPECIAL PROVISION (CAP CURB DROP INLET)	900.620	-
			8	8	EA	SPECIAL PROVISION (CORING CONCRETE)	900.620	-
			8	8	EA	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-
			1	1	EA	SPECIAL PROVISION (GNSS CONSTRUCTION INSPECTION EQUIPMENT)	900.620	-
			217	217	LF	SPECIAL PROVISION (BARRIER FOR TEMPORARY TRAFFIC PROTECTION)	900.640	-
			1	1	LS	SPECIAL PROVISION (GPS MACHINE CONTROL GRADING)	900.645	-
			132500	132500	SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	605
			2630	2630	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	30.7
			136800	136800	SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	1143
			4050	4050	TON	SPECIAL PROVISION (AGGREGATE TO MEET COLD MIXED GRADATION)	900.680	37.6
			1000	1000	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	EST.
			10	10	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE 1)	900.680	EST.
			22400	22400	TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	218
			28000	28000	TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)	900.680	288.2
			2060	2060	TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	25.1
			270	270	TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	3
			16500	16500	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT, COLD MIX WITH CEMENT)	900.683	77
			1650	1650	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT (RS-1H OR CRS-1H)	900.683	13.1
			1700	1700	CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	40.5

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)
11822.9	TON	WEARING COURSE
7137.1	TON	INTERMEDIATE COURSE
2708	TON	LEVELING COURSE
460.8	TON	SIDE ROADS
53.2	TON	PULL OFFS
218	TON	ROUNDING
22400	TON	TOTAL
		SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)
9102.2	TON	COLD MIX (3" LIFT)
18609.6	TON	COLD MIX ((2) 2" LIFTS)
288.2	TON	ROUNDING
28000	TON	TOTAL
		SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)
1000	TON	2014 LEVELING COURSE PAVEMENT
EST.	TON	ROUNDING
1000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: RANDOLPH
PROJECT NUMBER: STP 2932(1)

FILE NAME: z10c270.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: B. BRESLEND
QUANTITY SHEET 4

PLOT DATE: 6/5/2014
DRAWN BY: J. GOODALL
CHECKED BY: C. LATHROP
SHEET 18 OF 276