

DURABLE 4 INCH WHITE LINE (SEE OPTION ITEMS)
 STA. 314+25 - STA. 319+75 (SOLID LT & RT)

DURABLE 4 INCH YELLOW LINE, POLYUREA
 STA. 314+25 - STA. 319+75 (SOLID LT & RT)

6 INCH UNDERDRAIN PIPE
 STA. 314+25 - STA. 318+95 RT

TEMPORARY 4 INCH WHITE LINE, PAINT
 STA. 314+25 - STA. 319+75 (SOLID LT & RT)

TEMPORARY 4 INCH YELLOW LINE, PAINT
 STA. 314+25 - STA. 319+75 (SOLID LT & RT)

REMOVING SIGNS
 AS SHOWN - 2

SOLID ROCK EXCAVATION
 STA. 315+67 - STA. 316+36 RT

MILLED RUMBLE STRIPS
 STA. 314+25 - STA. 319+75 CTR

STONE FILL, TYPE I
 STA. 314+25 - STA. 318+80 LT
 STA. 319+20 - STA. 319+75 LT

GEOTEXTILE FOR SILT FENCE
 STA. 314+25 - STA. 318+80 LT
 STA. 319+20 - STA. 319+75 LT

GRUBBING MATERIAL (6")
 STA. 314+25 - STA. 318+80 LT
 STA. 319+20 - STA. 319+75 LT

CURVE #45
 DELTA = 25° 43' 09"
 D = 7° 38' 22"
 R = 750.00'
 T = 171.22'
 L = 336.66'
 E = 19.30'
 BANKING 0.080 FT/FT
 DESIGN SPEED 50 MPH
 SEE SUPERELEVATION DIAGRAMS
 FOR MORE INFORMATION

HVCNTRL 30
 N: 531544.938
 E: 1621520.487
 ELEV. 1031.015

35 STA. 319+03.74 RT 25.63' TO
 STA. 319+21.24 LT 27.06'
 REMOVE HEADWALL AND PIPE
 INSTALL NEW 18" CPEP (55' - 0")
 INV. IN = 1013.25'
 INV. OUT = 1009.75'

CURVE #46
 DELTA = 2° 42' 45"
 D = 0° 57' 18"
 R = 6000.00'
 T = 142.05'
 L = 284.05'
 E = 1.68'
 BANKING REVERSE CROWN
 DESIGN SPEED 50 MPH
 SEE SUPERELEVATION DIAGRAMS
 FOR MORE INFORMATION

SIGN LEGEND

- R = REMOVE
- R&S = REMOVE AND SALVAGE
- RET = RETAIN
- S = SALVAGE
- N = NEW
- B-B = BACK TO BACK
- = EXISTING
- = NEW



PROJECT NAME: RANDOLPH
 PROJECT NUMBER: STP 2932 (1)

FILE NAME: z10c270.dgn
 PROJECT LEADER: C. LATHROP
 DESIGNED BY: B. BRESLEND
 PROJECT LAYOUT SHEET 53

PLOT DATE: 6/5/2014
 DRAWN BY: B. BRESLEND
 CHECKED BY: C. LATHROP
 SHEET 84 OF 276

