DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHMS"-STANDARD HIGHWAY SIGNS AND MARKINGS			
							(LINE INTENTIONALLY LEFT BLANK)																							
NB	0.000	C	VD-024	60	7.5		SPRINGFIELD I ROCKINGHAM						1		X														
		C	VD-700	6	8		MILE MARKER 0050/1418/0000						1																
		C	VD-700	6	8		MILE MARKER 0050/1314/0885						1		X												THIS MILE MARKER IS ON ITS OWN POST, ADJACENT TO THE TOWN LINE SIGN; REMOVE ALL			
		C	VD-024	72	10		Springfield | Rockingham	5.00								2		X									INSTALL THE NEW SIGN CENTERED IN THE SAME POSITION AS THE REMOVAL;		11	
		C	VD-025	72	10		Windsor Co. | Windham Co.	5.00																			INSTALL THE NEW COUNTY LINE SIGN UNDER THE TOWN LINE SIGN		11	
		C	VD-700	6	10		0050 1418 0000 / 0050 1314 0885	0.42																			SPRINGFIELD MILE MARKER; INSTALL ON THE LEFT POST			E-138
		C	VD-700	6	10			0.42																			ROCKINGHAM MILE MARKER; INSTALL ON THE RIGHT POST			E-138
NB	1.625	A	R2-5A	24	30		REDUCED SPEED AHEAD						1		X														
NB	1.666	A	W12-2	36	36		14'-0"						1		X												EXISTING SIGN IS ON A SINGLE POST			
		A	W12-2	36	36			9.00								2		X									INSTALL THE NEW SIGN ON TWO NEW POSTS	X		
NB	1.742	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X												UNAUTHORIZED SIGN; EXCELLENT STOPPING SIGHT DISTANCE TO BUS STOP AT MP 1.800, REMOVE			
NB	1.830	A	W3-5	36	36		SPEED LIMIT 40	9.00								2		X									INSTALL 865 FT ± NORTH OF THE 14'-0" SIGN AT MP 1.666 / 160 FT± NORTH OF DRIVEWAY #192 AT MP 1.800	X		
NB	1.910	A	R2-1	24	30								1		X														
		A	R2-1	30	36		SPEED LIMIT 40	7.50								1		X									NOTE: THE FIRST SIGN IN THE REDUCED SPEED ZONE IS 30x36"		6	
							SHEET TOTALS	36.34	0.00	0	0	0	7	0	0	7		105										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	615.4	0.0	12.0	5.0	5.0	145	0.0	0.0	82		1230.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **SPRINGFIELD US-5 NB** PLOT DATE: **2/13/2012**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
SPRINGFIELD US-5 NORTHBOUND 1 SHEET **17** OF **162**