DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHMS"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.179	A	M5-1L	21	15		(CONT.)	2.19																		**WHITE ON BLUE** ADVANCE LEFT ARROW	X		
NB	2.192	A	W11-1	30	30		BICYCLE CROSSING SYMBOL						1		X											THIS SIGN WILL NOT BE REPLACED			
		A	D4-2L	30	36		PARK & RIDE	7.50								1		X								THE SIGN FURTHER NORTH AT MP 2.206 WILL BE REMOVED	X		
NB	2.206	A	D4-2L	24	30		PARK & RIDE w/ LEFT ARROW						1		X														
		A	M3-4	24	12		WEST EAST NORTH	2.00								2			X							#3	**GREEN ON WHITE** "WEST"; THIS NEW ASSEMBLY WILL BE BEHIND RAIL, 25 FT± SOUTH OF THE EXISTING ASSEMBLY	X		
		A	M1-5	24	24		VERMONT 11 VERMONT 11 5	4.00																		VERMONT ROUTE 11; INSTALL ALL SIGNS AS SHOWN IN THE SIGN LEGEND			E-136B
		A	M5-1L	21	15			2.19																		**GREEN ON WHITE** ADVANCE LEFT ARROW	X		
		A	M3-2	24	12		TO	2.00																		**GREEN ON WHITE** "EAST"	X		
		A	M1-5	24	24		INTERSTATE 91	4.00																		VERMONT ROUTE 11			E-136B
		A	M5-1R	21	15			2.19																		**GREEN ON WHITE** ADVANCE RIGHT ARROW	X		
		A	M3-1	24	12			2.00																		**BLACK ON WHITE** "NORTH"	X		
		A	M1-4	24	24			4.00																		US ROUTE 5	X		
		A	M5-1R	21	15			2.19																		**BLACK ON WHITE** ADVANCE RIGHT ARROW	X		
		A	M4-5	24	12			2.00																		**WHITE ON BLUE** "TO"	X		
		A	M1-1	24	24		(CONT. ON NEXT PAGE)	4.00																		INTERSTATE 91	X		
							SHEET TOTALS	40.26	0.00	0	0	0	2	0	0	3		45										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	615.4	0.0	12.0	5.0	5.0	145	0.0	0.0	82		1230.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **SPRINGFIELD US-5 NB** PLOT DATE: **2/13/2012**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
SPRINGFIELD US-5 NORTHBOUND 3 SHEET **19** OF **162**