DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHMS"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.332	A	W13-2	24	30		EXIT 30 MPH						1		X													
		A	W13-2	24	30		EXIT 30 MPH	5.00								1		X										X	
NB	2.364	A	OM1-1	18	18								1		X													
		A	OM1-1	18	18			2.25								1		X									STAND-ALONE OBJECT MARKER IN THE GORE FOR THE I-91 SB OFF-RAMP; INSTALL AT 4 FT VERTICAL CLEARANCE	X	
NB	2.405	A	VR-118L	36	48		THRU TRAFFIC KEEP LEFT						1		X													
		A	VR-118L	36	48		THRU TRAFFIC KEEP LEFT	12.00								2		X											7
NB	2.433	B	M3-3	24	12		SOUTH INTERSTATE 91	2.00								1		X									WHITE ON BLUE "SOUTH"	X	
		B	M1-1	24	24		SOUTH INTERSTATE 91	4.00																			THIS ASSEMBLY FACES SB TRAFFIC; INSTALL IN THE GORE FOR THE I-91 SB ACCESS RAMP	X	
		B	M6-1L	21	15		SOUTH INTERSTATE 91	2.19																			WHITE ON BLUE LEFT ARROW	X	
NB	2.440	J	R3-2	24	24		NO LEFT TURN SYMBOL						1		X												NOTE: THIS SIGN POST IS EMBEDDED IN THE GRASSY RAISED CENTER MEDIAN		
		J	OM1-1	18	18		OBJECT MARKER						1															
		K	R4-7	24	30		KEEP RIGHT SYMBOL (ON BACK)						1																
		K	OM1-1	18	18		OBJECT MARKER						1																
		J	R3-2	24	24			4.00								1		X									NO LEFT TURN SYMBOL FACES NB TRAFFIC (AT THE END OF THE RAISED MEDIAN)	X	
		J	OM1-1	18	18		(BACK-TO-BACK)	2.25																			OBJECT MARKER FACES NB TRAFFIC (CONT. ON NEXT PAGE)	X	
							SHEET TOTALS	33.69 SF	0.00 SF	0 EA	0 EA	0 EA	7 EA	0 EA	0 EA	6 EA		90 FT										
							TOWN DIRECTIONAL TOTALS	615.4	0.0	12.0	5.0	5.0	145	0.0	0.0	82		1230.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **SPRINGFIELD US-5 NB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
SPRINGFIELD US-5 NORTHBOUND 7

PLOT DATE: **2/13/2012**
DRAWN BY: **M. MILLER**
CHECKED BY: **A. GAMBLE**
SHEET **23** OF **162**