DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHMS"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.697	A	M1-4	24	24		Charlestown NH 2 NORTH 5 EAST VERMONT 11 (CONT.)	4.00																			US ROUTE 5	X		
		A	M3-2	24	12			2.00																			**GREEN ON WHITE** "EAST"; INSTALL ON THE RIGHT-SIDE POST	X		
		A	M1-5	24	24			4.00																			VERMONT ROUTE 11			E-136B
NB	2.725	A	D1-1A	72	12		SPEED LIMIT 40 CHARLESTOWN NH 2						1		X															
		A	R2-1	24	30			5.00								1		X										X		
NB	2.782	A	W11-1	24	24		BICYCLE SYMBOL				1	1	2 1		X						MILE MARKER PLAQUE SALVAGED ONTO THE NEW POST									
		A	W11-15	30	30	FYG	TRAIL X-ING 0050 1418 0280	6.25								1		X									SEE GENERAL NOTES, "SIGN DESIGN AND FABRICATION", #1	X		
		A	W11-15P	24	18	FYG		3.00																			SEE GENERAL NOTES, "SIGN DESIGN AND FABRICATION", #1	X		
NB	2.805	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X												YOUNGS GAS PLANT RD (TH-69)			
		C	VR-017	24	30			5.00								1		X											6	
NB	2.813	D	R1-1	30	30		STOP				1	1	2 1		X						MILE MARKER PLAQUE SALVAGED ONTO THE NEW POST						YOUNGS GAS PLANT RD (TH-69)			
		D	R1-1	30	30		0050 1418 0283	6.25								1		X										X		
NB	2.814	A	N/A	30	30		TRAIL HEAD PARKING ---> (BACK-TO-BACK)			1				X																
		B	N/A	30	30		<--- TRAIL HEAD PARKING			1																				
NB	2.827	C	R5-3	18	18		NO MOTOR VEHICLES			1				X													ON BIKE ROUTE			
							SHEET TOTALS	35.50	0.00	3	0	0	2 4	0	0	4		60											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	615.4	0.0	12.0	5.0	5.0	145	0.0	0.0	82		1230.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: SPRINGFIELD-HARTFORD
PROJECT NUMBER: STPG SIGN(33)

FILE NAME: SPRINGFIELD US-5 NB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
SPRINGFIELD US-5 NORTHBOUND 12

PLOT DATE: 2/13/2012
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE