DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHMS"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.828	A	D11-1	24	18		BIKE ROUTE			1				X														
		A	M6-4	12	9		DOUBLE ARROW			1																		
NB	2.830	D	R1-1	18	18		STOP			1				X												ON BIKE ROUTE			
NB	2.883	A	R2-1	24	30		SPEED LIMIT 40						1		X											WILL NOT BE REPLACED			
NB	2.947	A	M2-1	21	15		JCT						1		X											WILL NOT BE REPLACED			
		A	M1-4	24	24		US ROUTE 5						1																
		A	M3-1	24	12			2.00								2		X							#1	**BLACK ON WHITE** "NORTH"; USE A SIGN FRAME TO BRACE THE NEW ASSEMBLY	X		
		A	M1-4	24	24			4.00																		US ROUTE 5	X		
		A	M5-1L	21	15			2.19																		**BLACK ON WHITE** ADVANCE LEFT ARROW	X		
		A	M4-6	24	12			2.00																		**GREEN ON WHITE** "END"	X		
		A	M1-5	24	24			4.00																		VERMONT ROUTE 11			E-136B
NB	2.987	A	D1-1M	72	10		(UP) CHARLESTOWN NH 2						1		X														
		A	D2-1	72	10		(LEFT) WEATHERSFIELD BOW 8						1																
		A	D2-1	72	10		(LEFT) WHITE RIVER JCT 31						1																
		A	VD-700	6	8		MILE MARKER 0050/1418/0300				1		1														SALVAGE THE MILE MARKER TO THE NEW ASSEMBLY AT MP 2.996			
							SHEET TOTALS	14.19	0.00	3	1	0	7	0	0	2		30										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	615.4	0.0	12.0	5.0	5.0	145	0.0	0.0	82		1230.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **SPRINGFIELD US-5 NB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
SPRINGFIELD US-5 NORTHBOUND 13

PLOT DATE: **2/13/2012**
DRAWN BY: **M. MILLER**
CHECKED BY: **A. GAMBLE**
SHEET **29** OF **162**