DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHMS"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	3.041	B	M1-4	24	24		US ROUTE 5 (CONT.)						1																
		B	M6-3	21	15		UP ARROW						1																
		B	M3-4	24	12		WEST						1																
		B	M1-6	24	24		VERMONT ROUTE 11						1																
		B	M6-3	21	15		UP ARROW						1																
		B	M3-1	24	12		NORTH						1																
		B	M1-4	24	24		US ROUTE 5						1																
		B	M6-1R	21	15		RIGHT ARROW						1																
		A	M3-1	24	12			2.00								2			X						#3	**BLACK ON WHITE** "NORTH" (INSTALL THE US-5 SIGNS ON THE LEFT SIDE OF THE FRAME)	X		
		A	M1-4	24	24			4.00																			US ROUTE 5	X		
		A	M6-1L	21	15			2.19																			**BLACK ON WHITE** LEFT ARROW	X		
		A	M3-2	24	12			2.00																			**BLACK ON WHITE** "EAST" (INSTALL THE N.H. 11 SIGNS ON THE CENTER OF THE FRAME)	X		
		A	M1-6	24	24			4.00																			NH ROUTE 11			SG-1
		A	M6-3	21	15		(ALL 9 SIGNS BELOW ON BACK)	2.19																			**BLACK ON WHITE** UP ARROW	X		
		B	M3-3	24	12		(SEE NEXT PAGE)	2.00																			**BLACK ON WHITE** "SOUTH"	X		
							SHEET TOTALS	18.38 SF	0.00 SF	0 EA	0 EA	0 EA	8 EA	0 EA	0 EA	2 EA		30 FT									
							TOWN DIRECTIONAL TOTALS	615.4	0.0	12.0	5.0	5.0	145	0.0	0.0	82		1230.0									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **SPRINGFIELD US-5 NB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
SPRINGFIELD US-5 NORTHBOUND 15

PLOT DATE: **2/13/2012**
DRAWN BY: **M. MILLER**
CHECKED BY: **A. GAMBLE**
SHEET **31** OF **162**