DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHMS"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	3.041	B	M1-4	24	24		(CONT.)	4.00																		US ROUTE 5	X		
		B	M6-3	21	15			2.19																		**BLACK ON WHITE** UP ARROW	X		
		B	M3-4	24	12			2.00																		**GREEN ON WHITE** "WEST"	X		
		B	M1-5	24	24			4.00																		VERMONT ROUTE 11			E-136B
		B	M6-3	21	15			2.19																		**GREEN ON WHITE** UP ARROW	X		
		B	M3-1	24	12			2.00																		**BLACK ON WHITE "NORTH"**	X		
		B	M1-4	24	24			4.00																		US ROUTE 5	X		
		B	M6-1R	21	15			2.19																		**BLACK ON WHITE** RIGHT ARROW	X		
NB	3.052	B	R1-1	30	30		0050 1418 0306				1	1	1		X											MILE MARKER PLAQUE SALVAGED ONTO THE NEW POST	"GATEPOSTED" STOP SIGN AT JCT WITH VERMONT ROUTE 11; FACES SB US ROUTE 5 TRAFFIC			
		B	R1-1	30	30			6.25					1			1		X									X		
NB	3.063	A	M3-1	24	12		NORTH						1		X														
		A	M1-4	24	24		US ROUTE 5						1																
		A	VM-120	18	24		CT RIVER BYWAY				1		1														TO BE SALVAGED ONTO THE NEW ASSEMBLY AT THIS LOCATION			
		A	D6-4A	18	9		AMERICA'S BYWAYS (PLAQUE)				1		1														TO BE SALVAGED ONTO THE NEW ASSEMBLY AT THIS LOCATION			
		B	VR-040	24	24		THROUGH WAY ENDS HERE (ON BACK)						1														THIS SIGN WILL NOT BE REPLACED **(CONTINUED ON NEXT PAGE)**			
							SHEET TOTALS	28.82	0.00	0	23	01	76	0	0	1		15											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	615.4	0.0	12.0	5.0	5.0	145	0.0	0.0	82		1230.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **SPRINGFIELD US-5 NB** PLOT DATE: **2/13/2012**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
SPRINGFIELD US-5 NORTHBOUND 16 SHEET **32** OF **162**