DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	8.777	F	M2-1	21	15								1		X													
		F	M1-6	30	24						1	1	1 1							MILE MARKER PLAQUE WAS SALVAGED ONTO THE NEW POST								
		F	M2-1	21	15		JCT	2.19								1		X							**BLACK ON WHITE** "JCT"	X		
		F	M1-6	30	24		143 0050 1418 0880	5.00																	STATE NUMBERED TOWN HIGHWAY 143 (NOT A STATE ROUTE)			E-136C
~~SB~~	~~8.691~~	~~F~~	~~VD-062AS~~	~~72~~	~~16~~		~~BUSINESS DIRECTIONAL SIGN~~			~~1~~ 0				~~X~~						SIGN IS MISSING					SKYLINE NURSERY			
SB	8.617	F	D1-1M	72	10		SPRINGFIELD VIA 143 6 (45 DEG --->)						1		X													
		F	D1-1M	72	10		(<--- 45 DEG) SPRINGFIELD VIA US-5 8						1															
		F	VD1-1A	72	12		Springfield via US-5 8	6.00								2		X							NOTE: INSTALL AS SHOWN IN THE SIGN LEGEND		5	
		F	VD1-1A	72	12		Springfield via 143 6	6.00																	NEW DESTINATION SIGNS HAVE NEW SIGN CODES AND UPPER / LOWER CASE LETTERS (TYP)		15	
SB	8.590	F	M3-3	24	12		SOUTH						1		X													
		F	M1-4	24	24		US ROUTE 5						1															
		F	M6-2L	21	15		ANGLED LEFT ARROW						1															
		F	M3-4	24	12		WEST						1															
		F	M1-6	30	24		STATE NUMBERED TOWN HIGHWAY 143						1															
		F	M6-2R	21	15		ANGLED RIGHT ARROW						1															
SIGN SUMMARY SHEET							SHEET TOTALS	19.19	0.00	~~1~~ 0	~~1~~ 0	~~1~~ 0	~~1~~ 11	0	0	3		45										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	495.5	0.0	26.0	3.0	3.0	101	0.0	0.0	69		1035.0										

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **SPRINGFIELD US-5 SB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
SPRINGFIELD US-5 SOUTHBOUND 1

PLOT DATE: **2/9/2012**
DRAWN BY: **M. MILLER**
CHECKED BY: **A. GAMBLE**
SHEET **39** OF **162**