DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	3.085	F	M3-3	24	12		(CONT.)	2.00																		**BLACK ON WHITE** "SOUTH"	X		
		F	M1-4	24	24			4.00																		US ROUTE 5	X		
		F	M6-1R	21	15			2.19																		**BLACK ON WHITE** RIGHT ARROW	X		
SB	3.059	F	R1-1	30	30		STOP						1		X													
		F	R1-1	36	36			9.00								2		X								NOTE THE NEW SIGN IS LARGER; **MAINTAIN 10 FT MINIMUM DISTANCE TO UTILITY POLE**	X		
SB	3.051	F	R5-3	24	24		NO MOTOR VEHICLES			1				X												APPLIES TO SHARED USE BIKE ROUTE ADJACENT TO ROUTE 5			
		F	unknown	24	8		BEGIN			1																		
		F	unknown	24	18		BIKE ROUTE			1																		
		F	unknown	24	8		DOWNTOWN 3.9 UP ARROW			1																		
SB	3.032	F	M3-4	24	12		HOMEMADE SIGN 3 MILES TO TRAIL HEAD WEST						1 1		X												TRAIL HEAD SIGN WAS REMOVED			
		F	M1-6	24	24		VERMONT ROUTE 11						1																
		F	M3-3	24	12		SOUTH						1																
		F	M1-4	24	24		US ROUTE 5						1																
		F	VM-120	18	24		CT RIVER BYWAY				1	1	1														TO BE SALVAGED AT THIS LOCATION ONTO THE NEW POST			
		F	D6-4A	18	9		AMERICA'S BYWAYS (PLAQUE) (CONT. ON NEXT PAGE)				1	1	1														TO BE SALVAGED AT THIS LOCATION ONTO THE NEW POST			
							SHEET TOTALS	17.19	0.00	4	2	2 0	8 7	0	0	2		30											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	495.5	0.0	26.0	3.0	3.0	101	0.0	0.0	69		1035.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **SPRINGFIELD US-5 SB** PLOT DATE: **2/9/2012**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
SPRINGFIELD US-5 SOUTHBOUND 7 SHEET **45** OF **162**