DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	2.899	F	W11-15P	24	18	FYG	TRAIL X-ING (CONT.)	3.00																			SEE SHEET 2, SIGN DESIGN AND FABRICATION, NOTE #1	X		
SB	2.882	F	VR-048	24	30		STATE LAW STOP FOR SCHOOL BUS FLASHING RED LIGHTS						1		X														
SB	2.862	F	W3-1	18	18		STOP AHEAD (FOR BIKE PATH)			1				X													LOCATED ON THE BIKE PATH; RETAIN			
SB	2.855	F	D11-1	24	18		BIKE ROUTE			1				X															
		F	M6-4	12	9		DOUBLE ARROW			1																			
SB	2.853	E	R5-3	24	24		NO MOTOR VEHICLES (FOR BIKE PATH)				1		1		X												FLANGE SIGN POST IS BADLY TWISTED			
		E	R5-3	24	24		NO MOTOR VEHICLES (FOR BIKE PATH)					1				1		X									SALVAGE THE SIGN ONTO A NEW POST; SIGN FACES SB ON BIKE PATH			
SB	2.852	F	R1-1	18	18		STOP (FOR BIKE PATH)			1				X													LOCATED ON THE BIKE PATH; RETAIN			
SB	2.842	F	VR-654	24	24		NO DWI (SYMBOL)						1		X														
		F	VR-655	24	18		STRICTLY ENFORCED (PLAQUE)						1																
SB	2.798	F	M2-1	21	15		JCT			1				X															
		F	M1-1	24	24		INTERSTATE 91			1																			
SB	2.735	F	D1-1A	72	12		(UP ARROW) SPRINGFIELD 4						1		X														
		F	D1-1A	72	12		(UP ARROW) BELLOWS FALLS 10						1																
		F	D1-1A	72	12		(LEFT ARROW) WHITE RIVER JCT 31 (CONT. ON NEXT PAGE)						1																
							SHEET TOTALS	3.00	0.00	6	1	1	7	0	0	1			15										
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT										
							TOWN DIRECTIONAL TOTALS	495.5	0.0	26.0	3.0	3.0	101	0.0	0.0	69			1035.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **SPRINGFIELD US-5 SB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
SPRINGFIELD US-5 SOUTHBOUND 9

PLOT DATE: **2/9/2012**
DRAWN BY: **M. MILLER**
CHECKED BY: **A. GAMBLE**
SHEET **47** OF **162**