DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SPRINGFIELD SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	2.187	F	R2-1	24	30		SPEED LIMIT 40			1				X															
SB	2.154	F	VM-120	18	24		CT RIVER BYWAY			1				X															
		F	D6-4A	18	9		AMERICA'S BYWAYS (PLAQUE)			1																			
SB	1.903	F	R2-1	24	30		SPEED LIMIT 50						1		X														
		F	VW16-18P	24	12	FY	STATE LAW / SPEED LIMIT 50 / UNLESS OTHERWISE POSTED	2.00								1		X									STATE LAW SIGN ONLY: BLACK ON FLUORESCENT YELLOW; INSTALL ON TOP		7	
		F	R2-1	24	30			5.00																			SPEED LIMIT 50	X		
		F	R2-5P	24	18			3.00																			USE INTERIM DESIGN IN 2004 SHS FOR THIS NEW 2009 MUTCD SIGN; INSTALL ON BOTTOM		7	
SB	1.845	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X												UNAUTHORIZED SIGN; EXCELLENT STOPPING SIGHT DISTANCE TO BUS STOP AT MP 1.800, REMOVE			
SB	1.742	F	VR-114	48	60		STATE OF VERMONT SPEED LIMIT 50 UNLESS OTHERWISE POSTED RADAR ENFORCEMENT						1		X															
SB	1.692	F	W12-2	36	36		14'-0"						1		X														
		F	W12-2	36	36			9.00								2		X										X		
SB	1.521	F	W5-1	30	30		ROAD NARROWS						1		X												REFERENCE THIS LOCATION FOR THE NEXT SIGN			
SB	1.474	F	VW-619	36	36		SHOULDER NARROWS	9.00								2		X									INSTALL THIS NEW SIGN 250 FT± SOUTH OF THE REMOVED "ROAD NARROWS" SIGN AT MP 1.521		8	
SB	1.226	F	VW-060	30	30		HIDDEN DRIVE (SINGULAR)						1		X												EXISTING HAS SINGULAR "DRIVE"			
		F	VW-060	30	30		HIDDEN DRIVES	6.25								1		X									NEW HAS PLURAL "DRIVES"			E-154
							SHEET TOTALS	34.25	0.00	3	0	0	6	0	0	6		90										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	495.5	0.0	26.0	3.0	3.0	101	0.0	0.0	69		1035.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **SPRINGFIELD US-5 SB** PLOT DATE: **2/9/2012**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
SPRINGFIELD US-5 SOUTHBOUND 16 SHEET **54** OF **162**