



DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	SHSM	PROJECT SHEET #	STANDARD SHEET #
																	(LB / FT)				(LB / FT)								
<b>WEATHERSFIELD NB</b>							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS							
							(THIS LINE INTENTIONALLY LEFT BLANK)																						
NB	0.000	C	VD-024	60	7.5		WEATHERSFIELD I SPRINGFIELD						1		X														
		C	VD-700	6	10		0050 / 1420 / 0000 (Weathersfield MM)				1		1																
		C	VD-700	6	10		0050 / 1418 / 0912 (Springfield MM)				1		1																
		C	VD-024	72	10		<b>Weathersfield   Springfield</b>	5.00							2	X								INSTALL THE NEW SIGN ON TWO POSTS CENTERED IN THE EXACT POSITION AS THE REMOVED TOWN LINE SIGN		11			
		C	VD-700	6	10		0050 / 1420 / 0000 (Weathersfield MM)					1												WEATHERSFIELD MILE MARKER, INSTALL ON THE LEFT SIDE POST					
		C	VD-700	6	10		0050 / 1418 / 0912 (Springfield MM)					1												SPRINGFIELD MILE MARKER, INSTALL ON THE RIGHT SIDE POST					
NB	0.000	A	VD-700	6	8		0050 / 1418 / 0912 (Springfield MM)						1		X									THIS IS A 2nd SPRINGFIELD MILE MARKER ON A DELINEATOR POST BEHIND THE TOWN LINE SIGN; REMOVE ALL					
NB	0.803	A	W3-5	36	36		SPEED REDUCTION 40-MPH			1					X									ASTM TYPE IV, AS-NEW, RETAIN					
NB	0.840	A	VD-018	30	18		WEATHERSFIELD BOW ASCUTNEY 4			1					X									ASTM TYPE IV, AS-NEW, RETAIN					
NB	0.922	A	R2-1	24	30								1		X									NOTE: THE NEW SIGN IS LARGER, FIRST SIGN IN THE REDUCED SPEED ZONE 40		6			
		A	R2-1	30	36			7.50								1	X												
NB	1.283	C	VR-017	24	24								1		X									FERRY RD (TH-53)					
		C	VR-017	24	30			5.00								1	X									6			
NB	1.292	D	R1-1	30	30		2 EA <b>FERRY ROAD</b> STOP (CONT. ON NEXT PAGE)				2	2	3										STREET SIGNS SALVAGED ONTO THE NEW POSTS		FERRY RD (TH-53)				
<b>SIGN SUMMARY SHEET</b>							<b>SHEET TOTALS</b>	17.50	0.00	2	4	4	9	0	0	4	60.0	0	0.0	0.0	0.0	0.0	PROJECT NAME: <b>SPRINGFIELD-HARTFORD</b>	PROJECT NUMBER: <b>STPG SIGN(33)</b>					
VERMONT AGENCY OF TRANSPORTATION							<b>TOWN DIRECTIONAL TOTALS</b>	367.0	0.0	11	4	4	89	0	0	48	720.0	0		0.0			FILE NAME: <b>WEATHERSFIELD US-5 NB</b>	PROJECT MANAGER: <b>A. GAMBLE</b>	PLOT DATE: <b>2/13/2012</b>				
																					DESIGNED BY: <b>M. MILLER</b>	CHECKED: <b>A. GAMBLE</b>	DRAWN BY: <b>M. MILLER</b>						
																						WEATHERSFIELD US-5 NB 1	SHEET <b>55</b>	OF <b>162</b>					