DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WEATHERSFIELD NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	5.330	A	D2-1S	72	12		MT ASCUTNEY SKI AREA 7 (CONT.)						1													THIS SIGN WILL NOT BE REPLACED; THE RESORT IS CLOSED			
		A	D9-2	24	24		HOSPITAL (SYMBOL)						1																
		A	VD2-1	72	12		Windsor 5 Brownsville 7	6.00								2		X								THE NEW DESTINATION SIGNS WILL HAVE NEW SIGN CODES AND UPPER / LOWER CASE LETTERS		16	
		A	VD2-1	72	12			6.00																		INSTALL THE SIGNS AS SHOWN IN THE SIGN LEGEND		16	
		A	D9-2	24	24			4.00																		INSTALL THIS HOSPITAL TRAIL BLAZER SIGNS ON THE LEFT POST	X		
		A	M6-3	21	15			2.19																		**WHITE ON BLUE;** UP ARROW	X		
NB	5.426	A	VD1-2R	72	20		<--- WEATHERSFIELD SCHOOL			1				X															
NB	5.476	A	R2-1	24	30		SPEED LIMIT 35			1				X															
NB	5.620	A	R2-1	24	30		SPEED LIMIT 40			1				X															
NB	5.819	A	W2-1M	30	30								1		X														
		A	W2-7L	30	30			6.25								1		X										X	
NB	5.972	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS NO OUTLET				I	I	I 1		X											CHERRY LANE (TH-108)			
		C	VR-017	24	30			5.00								1		X								NO OUTLET SIGN WAS SALVAGED ONTO THE NEW SEPARATE POST.		6	
NB	5.978	D	R1-1	30	30								1		X											CHERRY LANE (TH-108)			
		D	R1-1	30	30		STOP CHERRY LANE - 2 EA.	6.25			2	2	2			1		X								STREET SIGN SALVAGED ONTO THE NEW POST	X		
							SHEET TOTALS	35.69	0.00	3	30	30	05	0	0	5		75.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	367.0	0.0	11	4	4	89	0	0	48		720.0		0		0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **WEATHERSFIELD US-5 NB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
WEATHERSFIELD US-5 NB 10

PLOT DATE: **2/13/2012**
DRAWN BY: **M. MILLER**
CHECKED **A. GAMBLE**
SHEET **64** OF **162**