DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WEATHERSFIELD NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	6.264	A	M1-5	24	24		(CONT.)	4.00																		VERMONT ROUTE 12			E-136B
		A	M6-3	21	15			2.19																		**GREEN ON WHITE**; UP ARROW	X		
NB	6.307	A	M3-1	24	12		NORTH						1		X													
		A	M1-4	24	24		US ROUTE 5						1															
		A	M3-1	24	24		NORTH						1															
		A	M1-5	24	24		VERMONT ROUTE 12						1															
		A	M3-1	24	12			2.00								2		X						**BLACK ON WHITE**; "NORTH"; INSTALL THE NEW SIGNS SIDE-BY-SIDE, AS SHOWN IN THE SIGN LEGEND	X		
		A	M1-4	24	24			4.00																		US ROUTE 5	X		
		A	M3-1	24	12			2.00																		**GREEN ON WHITE**; "NORTH"	X		
		A	M1-5	24	24			4.00																		VERMONT ROUTE 12			E-136B
NB	6.330	A	W1-2L	30	30		LEFT CURVE						1		X											THIS SIGN WILL BE REPLACED FURTHER NORTH AT MP 6.383			
		A	R2-1	24	30			5.00								1		X						(NOTE: THE SPEED LIMIT 40 AND LEFT CURVE SIGN ARE SWAPPING POSITIONS AT MP 6.330 and 6.383)	X		
NB	6.383	A	R2-1	24	30		SPEED LIMIT 40						1		X													
		A	W1-2L	30	30			6.25			I	I	I			1		X						MILE MARKER PLAQUE WAS SALVAGED ONTO THE NEW POST	X		
NB	6.425	A	W1-6 L	48	24		LARGE ARROW LEFT (CONT. ON NEXT PAGE)						1		X													
SIGN SUMMARY SHEET							SHEET TOTALS	29.44	0.00	0	0	0	8 7	0	0	4		60.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	367.0	0.0	11	4	4	89	0	0	48		720.0		0		0.0						

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**
FILE NAME: **WEATHERSFIELD US-5 NB** PLOT DATE: **2/13/2012**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED **A. GAMBLE**
WEATHERSFIELD US-5 NB 13 SHEET **67** OF **162**