DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WINDSOR NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.970	A	R2-1	24	30		SPEED LIMIT 40						1		X														
NB	1.257	A	M3-1	24	12		NORTH				1		1		X														
		A	M1-4	24	24		US ROUTE 5				1		1																
		A	M3-1	24	12		NORTH				1		1																
		A	M1-5	24	24		VERMONT ROUTE 12				1		1																
		A	M3-1	24	12							1				2		X							#1	**BLACK ON WHITE,** "NORTH"; SALVAGE THE EXISTING SIGNS ONTO NEW POSTS WITH A NEW SIGN FRAME			
		A	M1-4	24	24			4.00				~~1~~	1									SIGN WAS REPLACED DUE TO DAMAGE					US ROUTE 5			
		A	M3-1	24	12							1															**GREEN ON WHITE,**"NORTH"			
		A	M1-5	24	24							1															VERMONT ROUTE 12			
NB	1.301	A	R2-1	24	30		SPEED LIMIT 40			1				X															
NB	1.589	A	R2-1	24	30		SPEED LIMIT 40			1				X															
NB	1.836	A	W1-4L	30	30		LEFT REVERSE CURVE						1		X														
NB	1.861	A	W1-4L	30	30			6.25								1		X									INSTALL THE NEW SIGN 130 FT± NORTH OF THE PREVIOUS POSITION AT MP 1.836	X		
NB	2.030	A	R2-1	24	30		SPEED LIMIT 40			1				X															
NB	2.221	A	W1-4L	30	30		LEFT REVERSE CURVE						1		X												TO BE REPLACED FURTHER NORTH AT MP 2.250			
SIGN SUMMARY SHEET							SHEET TOTALS	6.25	0.00	3	4	~~3~~4	~~8~~7	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	436.9	0.0	16	12	12	100	0	0	61		915.0		0	0.0								

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**
FILE NAME: **WINDSOR US-5 NB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
WINDSOR US-5 NB 2
PLOT DATE: **2/13/2012**
DRAWN BY: **M. MILLER**
CHECKED **A. GAMBLE**
SHEET **83** OF **162**