DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WINDSOR NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	6.077	A	D6-4A	18	9		AMERICA'S BYWAYS (PLAQUE) (CONT.)			1																			
NB	6.202	A	VW-092	30	30		UNSAFE TO PASS						1		X														
NB	6.417	A	W1-2R	30	30		RIGHT CURVE						1		X												THIS ASSEMBLY TO BE REPLACED FURTHER AHEAD AT MP 6.446±			
		A	W13-1P	18	18		35-MPH (PLAQUE)						1																
NB	6.460	A	W1-2R	30	30			6.25								1		X									INSTALL 225 FT± NORTH OF THE PREVIOUS LOCATON AT MP 6.417	X		
		A	W13-1P	18	18			2.25																			NOTE: INCREASE IN SPEED ON ADVISORY PLAQUE	X		
NB	6.492	C	VR-017	24	30						I	0	1		X											SALVAGE STREET SIGN TO STOP SIGN FOR BETTER VISIBILITY			
		C	VR-017	24	30			5.00								1		X									RUTH H. CARNEY DR (TH-77)		6	
NB	6.509	D	R1-1	30	30		RUTH H. CARNEY DR. 				0	I	2 1		X												RUTH H. CARNEY DR (TH-77)			
		D	R1-1	30	30			6.25								1		X										X		
NB	6.520	A	VW-619	30	30		SHOULDER NARROWS						1		X												TO BE REPLACED AT MP 6.568±			
NB	6.568	A	W11-7	30	30		EQUESTRIAN SYMBOL						1		X												THIS EXISTING ASSEMBLY IS NO LONGER VALID			
		A	W7-3A	24	18		NEXT 1 MILE (PLAQUE)						1																
		A	VW-619	36	36			9.00								2		X									INSTALL IN THE SAME POSITION AS THE EQUESTRIAN SIGNS REMOVAL		8	
SIGN SUMMARY SHEET							SHEET TOTALS	28.75	0.00	1	I 0	I 0	98	0	0	5		75.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	436.9	0.0	16	12	12	100	0	0	61		915.0		0		0.0							

PROJECT NAME: SPRINGFIELD-HARTFORD
PROJECT NUMBER: STPG SIGN(33)

FILE NAME: WINDSOR US-5 NB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
WINDSOR US-5 NB 15

PLOT DATE: 2/13/2012
DRAWN BY: M. MILLER
CHECKED A. GAMBLE
SHEET 96 OF 162