DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WINDSOR SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	3.713	F	unknown	12	18		TWO HOUR PARKING 9AM - 7PM			1				X															
		F	R7-8	12	18		RESERVED HANDICAP PARKING			1																			
SB	3.709	F	unknown	30	36		TURNING TRAFFIC MUST YIELD TO PEDS			1				X															
SB	3.693	G	R10-11A	24	24		NO TURN ON RED			1				X													BANDED ONTO SIGNAL MAST			
SB	3.683	F	unknown	12	18		TWO HOUR PARKING 9AM - 7PM			1				X													BANDED ONTO LIGHT POLE			
SB	3.647	F	W11-2	30	30		PEDESTRIAN SYMBOL						1		X												BANDED ONTO LIGHT POLE			
		F	W11-2	30	30	FYG		6.25								1		X									ATTACH BOTH SIGNS TO LIGHT POLE; PROVIDE 7 FT MIN. VERTICAL CLEARANCE, SIGNS WILL OVERHANG SIDEWALK	X		
		F	W16-7P	24	12	FYG		2.00																				X		
SB	3.616	G	R7-1	18	24		NO PARKING w/ LEFT ARROW				1		1		X															
		G	R7-1	18	24		NO PARKING w/ LEFT ARROW					1				1		X									SALVAGE THE SIGN ONTO A NEW POST			
SB	3.606	G	unknown	18	24		NO TRUCK PARKING			1				X													BANDED ONTO LIGHT POLE			
SB	3.561	F	W11-2	30	30		PEDESTRIAN SYMBOL						1		X															
		F	R7-8	12	18		RESERVED HANDICAP PARKING				1		1														NOTE: CURRENTLY INSTALLED IN "F" POSITION; TO BE SALVAGED TO "G" POSITION			
		F	W11-2	30	30	FYG		6.25								1		X									PROVIDE 7 FT MINIMUM VERTICAL CLEARANCE IF SIGNS OVERHANG THE SIDEWALK	X		
		F	W16-7P	24	12	FYG	(CONT. ON NEXT PAGE)	2.00																				X		
							SHEET TOTALS	16.50	0.00	6	2	1	4	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	491.1	0.0	35	13	13	91	0	0	66		990.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: SPRINGFIELD-HARTFORD
PROJECT NUMBER: STPG SIGN(33)

FILE NAME: WINDSOR US-5 SB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
WINDSOR US-5 SB 6

PLOT DATE: 2/13/2012
DRAWN BY: M. MILLER
CHECKED A. GAMBLE
SHEET 102 OF 162