DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WINDSOR SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	3.366	H	M1-4	24	24		(CONT.)	4.00																		US ROUTE 5	X		
		H	M6-1R	21	15			2.19																		**BLACK ON WHITE**; RIGHT ARROW	X		
SB	3.319	F	M4-5	24	12			2.00								1		X								**WHITE ON BLUE**, "TO"; INSTALL BEHIND BRIDGE RAIL 250 FT± SOUTH OF THE ROUTE MARKERS AT MP 3.366	X		
		F	M3-3	24	12			2.00																		**WHITE ON BLUE**, "SOUTH"	X		
		F	M1-1	24	24			4.00																		INTERSTATE 91	X		
SB	3.285	E	M1-4	24	24		US ROUTE 5						1		X											BOTH SIGNS FACE NB US ROUTE 5 TRAFFIC; REMOVE ALL			
		E	M1-6	24	24		ROUTE 12						1																
SB	3.282	G	R5-1	30	30			6.25								1		X								MAPLE ST (TH-45); INSTALL NEW ON THE NORTH SIDE OF THE STREET	X		
SB	3.276	F	D3-1	UNK	UNK		MAPLE ST			1				X												MAPLE ST (TH-45); STREET NAME SIGN ON TOP			
		F	R6-1L	36	12		ONE WAY LEFT			1																FACES SB US ROUTE 5 TRAFFIC			
		E	R6-1R	36	12		ONE WAY RIGHT (ON BACK)			1																FACES NB US ROUTE 5 TRAFFIC			
		G	R5-1	30	30		DO NOT ENTER						1													REMOVE, BEING REPLACED ON A NEW POST ON THE NORTH SIDE OF THE STREET			
		H	R1-1	30	30		STOP			1																			
SB	3.257	G	VR-017	24	30			5.00								1		X								LOWELL ST (TH-49)		6	
SB	3.251	F	D3-1	UNK	UNK		LOWELL ST (CONT. ON NEXT PAGE)			1	I	I	I	~~X~~	X											STREET SIGNS WERE SALVAGED ONTO THE NEW POST STREET SIGN FACES SB US ROUTE 5; ~~RETAIN~~ EXISTING POST REMOVE			
SIGN SUMMARY SHEET							SHEET TOTALS	25.44	0.00	5	~~1~~ 0	~~1~~ 0	~~43~~ 3	0	0	3		~~45.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	491.1	0.0	35	13	13	91	0	0	66		990.0		0	0.0								

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **WINDSOR US-5 SB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
WINDSOR US-5 SB 12

PLOT DATE: **2/13/2012**
DRAWN BY: **M. MILLER**
CHECKED **A. GAMBLE**
SHEET **108** OF **162**