DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WINDSOR SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	0.389	F	W1-2R	30	30		0050 1423 0040						1		X													
		F	W1-2R	30	30			6.25			I	I	I			1		X								MILEMARKER WAS SALVAGED ONTO THE NEW POST	X		
SB	0.312	F	VW-202	30	30		TRUCKS ENTERING			1				X														
SB	0.236	F	R2-1	24	30			5.00								1		X								INSTALL 400 FT± SOUTH OF THE TRUCKS ENTERING SIGN AT MP 0.312	X		
SB	3.420	F	R3-8	30	30					I				X												SIGN RETAINED - NOT ORIGINALLY ON THE PLANS.			
							SHEET TOTALS	11.25 SF	0.00 SF	1 EA	0 EA	0 EA	2 EA	0 EA	0 EA	2 EA		30.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB				
							TOWN DIRECTIONAL TOTALS	491.1	0.0	35	13	13	91	0	0	66		990.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: SPRINGFIELD-HARTFORD
PROJECT NUMBER: STPG SIGN(33)

FILE NAME: WINDSOR US-5 SB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
WINDSOR US-5 SB 17

PLOT DATE: 2/13/2012
DRAWN BY: M. MILLER
CHECKED A. GAMBLE
SHEET 113 OF 162