DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
HARTLAND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.287	A	M2-1	21	15		JCT						1		X														
		A	M1-1	24	24		INTERSTATE 91						1																
		A	M2-1	21	15			2.19								1		X									**WHITE ON BLUE**; "JCT"	X		
		A	M1-1	24	24			4.00																			INTERSTATE 91	X		
NB	0.405	A	VD1-1A	72	10		(UP ARROW) ASCUTNEY 10			1				X													ALL SIGNS REPLACED IN 2009			
		A	VD1-1A	72	10		(UP ARROW) SPRINGFIELD 23			1																			
		A	VD1-1A	72	10		WHITE RIVER JCT 9 (90 DEG) --->			1																			
NB	0.425	A	R8-3A	24	24		NO PARKING SYMBOL						1		X														
		A	VR-644P	24	12		BEGIN PLAQUE						1																
		A	R8-3A	24	24			4.00								1		X									REPLACE SIGNS IN THE SAME POSITION AS THE REMOVAL	X		
		A	M4-14	24	12			2.00																			**BLACK ON WHITE**, "BEGIN"; 2009 MUTCD SIGN CODE	X		
NB	0.449	A	D4-2L	30	36		PARK & RIDE w/ LEFT ARROW						1		X														
		A	VD-365	30	6		1-800-685-RIDE						1														THE PHONE NUMBER PLAQUE IS NOT BEING REPLACED			
		A	D4-2L	30	36			7.50								1		X										X		
NB	0.463	C	VR-017	24	30		42ND ST – TH #42 LEGAL LOAD LIMIT 24,000 POUNDS (CONT. ON NEXT PAGE)						1		1												STREET SIGN REMOVED AND SALVAGED. SEE NEXT SHEET.		42ND ST (TH-42); **EXISTING SIGN AND POST ARE MISSING**			
SIGN SUMMARY SHEET							SHEET TOTALS	19.69	0.00	3	0	0	7 ~~6~~	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	505.1	0.0	53	3	3	92	0	0	86		1290.0		0		0.0							

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **HARTLAND US-5 NB** PLOT DATE: **2/14/2012**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED **A. GAMBLE**
HARTLAND US-5 NB 2 SHEET **115** OF **162**