DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
HARTLAND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.535	A	R2-1	24	30		SPEED LIMIT 45						1		X														
		A	R2-1	24	30			5.00								1		X										X	
NB	2.797	A	R2-1	24	30		SPEED LIMIT 50						1		X														
		A	R2-1	24	30			5.00								1		X										X	
NB	3.529	A	W1-2R	30	30			6.25								1		X									90' S. OF, AND ACCROSS INSTALL ~~ACROSS~~ FROM POLE #261/40/FIBER OPTIC WARNING; LOCATION IS 900 FT± SOUTH OF JCT WITH GILSON RD (TH-78)	X		
NB	3.716	A	OM3-R	12	36								1	X													RETAIN THE EXISTING POST BEHIND BRIDGE RAIL; FACES NB TRAFFIC			
		A	OM3-R	12	36			3.00																				X	
NB	3.797	B	OM3-L	12	36								1	X													RETAIN THE EXISTING POST BEHIND BRIDGE RAIL; FACES SB TRAFFIC			
		B	OM3-L	12	36			3.00																				X	
NB	3.820	A	W1-2L	30	30			6.25								1		X									INSTALL 50 FT± SOUTH OF THE TRUCKS ENTERING SIGN AT MP 3.830	X		
		A	W13-1P	18	18		40 MPH	2.25																				X	
NB	3.830	A	VW-202	30	30		TRUCKS ENTERING						1		X														
NB	3.839	A	OM3-R	12	36																						EXISTING SIGN AND POST ARE MISSING			
		A	OM3-R	12	36		BRIDGE 62A US 5 BRIDGE SIGN WAS RETAINED	3.00								1		X									FACES NB TRAFFIC	X		
NB	3.861	B	OM-3L	12	36		(CONT. ON NEXT PAGE)						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	33.75 SF	0.00 SF	0 EA	0 EA	0 EA	6 EA	0 EA	0 EA	5 EA		75.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	505.1	0.0	53	3	3	92	0	0	86		1290.0		0	0.0								

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**

FILE NAME: **HARTLAND US-5 NB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
HARTLAND US-5 NB 12

PLOT DATE: **2/14/2012**
DRAWN BY: **M. MILLER**
CHECKED **A. GAMBLE**
SHEET **125** OF **162**