DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
HARTLAND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	5.966	B	OM-3L	12	36								1	X													RETAIN THE EXISTING POST BEHIND RAIL			
		B	OM3-L	12	36			3.00																			FACES SB TRAFFIC	X		
NB	6.015	A	R2-1	24	30						I	I	I		X														
		A	R2-1	24	30		0050 1409 0600	5.00					1			1		X									X		
NB	6.085	A	W11-2	30	30		PEDESTRIAN SYMBOL (NON FLUORESCENT)						1		X														
		A	W11-2	30	30	FYG		6.25								1		X									BOTH NEW SIGNS HAVE FLUORESCENT YELLOW-GREEN BACKGROUND SHEETING	X		
		A	W16-4P	30	24	FYG		5.00																					8
NB	6.121	C	VR-017	24	30																						MILL ST (TH-15); SIGN AND POST ARE MISSING			
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X											6
NB	6.131	D	R1-1	24	24		STOP						1		X												MILL ST (TH-15)			
		C	unknown	24	18		MILL ST. TH 15 NO TRUCKS				2	2	2 1														NOT A STATE ENDORSED SIGN; REMOVE THIS SIGN			
		C	unknown	12	18		DOG ORDINANCE SIGN				1		1														THIS SIGN TO BE SALVAGED ONTO THE BACK SIDE OF THE STOP SIGN			
		D	R1-1	30	30		(BACK TO BACK)	6.25								1		X										X		
		C	unknown	12	18		DOG ORDINANCE SIGN					1															SALVAGE CENTERED ON THE BACK OF THE NEW STOP SIGN			
NB	6.132	A	R8-3A	24	24		0050 1409 0614 NO PARKING SYMBOL (CONT. ON NEXT PAGE)				I	I	I 1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	30.50	0.00	0	5 ~~1~~	5 ~~1~~	11 ~~7~~	0	0	4		60.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	505.1	0.0	53	3	3	92	0	0	86		1290.0		0		0.0							

PROJECT NAME: SPRINGFIELD-HARTFORD
PROJECT NUMBER: STPG SIGN(33)

FILE NAME: HARTLAND US-5 NB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
HARTLAND US-5 NB 14

PLOT DATE: 2/14/2012
DRAWN BY: M. MILLER
CHECKED A. GAMBLE
SHEET 127 OF 162