DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
HARTLAND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	6.655	D	R1-1	24	24		STOP						1		X												COUTERMARSH ST (TH-79)			
		D	R1-1	30	30			6.25								1		X									FOR THE NORTHERLY APPROACH	X		
NB	6.694	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS ROCKWOOD ST TH #84 2 EA	5.00			2		2			1		X									ROCKWOOD ST (TH-84); INSTALL ON THE SOUTH SIDE OF TH-84		6	
NB	6.698	C	VR-017	24	24		0050 1409 0670 LEGAL LOAD LIMIT 24,000 POUNDS						1		X												ROCKWOOD ST (TH-84); EXISTING SIGNS ARE INSTALLED BACK TO BACK			
		D	R1-1	24	24		STOP (INSTALLED BACK-TO-BACK WITH ABOVE)				1		1																
		D	OM3-C	12	36			3.00				1				1		X									INSTALL AT 4 FT VERTICAL CLEARANCE IN "D" POSITION IN FRONT OF THE POLE TO HELP WARN OF THE POLE	X		
NB	6.702	D	R1-1	30	30		STOP	6.25				2 1				1		X									**INSTALL NEW ON THE NORTH SIDE OF TH-84** (DO NOT REPLACE IN THE POSITION OF THE REMOVAL)	X		
NB	6.721	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		X									INSTALL 110 FT± NORTH OF TH-84; MAINTAIN 10 FT MIN. TO UTILITY POLE	X		
NB	6.894	A	W1-5L	30	30		WINDING CURVES LEFT SYMBOL						1		X												TO BE REPLACED FURTHER NORTH AT MP 6.916			
		A	W13-1	18	18		40 MPH (PLAQUE)						1																
NB	6.916	A	W1-5L	36	36			9.00								2		X									INSTALL ~~115~~ 90 FT± NORTH OF THE REMOVAL AT MP 6.894; NOTE THIS SIGN IS LARGER	X		
		A	W7-3aP	24	18		NEXT ¾ MILE	3.00																			SINGULAR "MILE"; INSTALL PLAQUE ON LEFT SIDE POST		8	
NB	7.025	A	R2-1	24	30								1		X															
		A	R2-1	24	30		SPEED LIMIT 50	5.00								1		X										X		
NB	7.138	A	VW-619	36	36		SHOULDER NARROWS	9.00								2		X									INSTALL 240 FT± SOUTH OF THE SHOULER NARROWS SIGN AT MP 7.183; THIS NEW SIGN IS LARGER		8	
SIGN SUMMARY SHEET							SHEET TOTALS	51.50	0.00	0	~~3~~ 0	~~3~~ 0	~~9~~ 6	0	0	10		150.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	505.1	0.0	53	3	3	92	0	0	86		1290.0		0	0.0								

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**
FILE NAME: **HARTLAND US-5 NB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
PLOT DATE: **2/14/2012**
DRAWN BY: **M. MILLER**
CHECKED **A. GAMBLE**
HARTLAND US-5 NB 17
SHEET **130** OF **162**