DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
HARTLAND SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	2.134	F	W1-10MR	30	30		CURVE RIGHT w/ MODIFIED DUAL SIDE ROAD LEFT SYMBOL						1		X														
SB	2.116	F	W1-10R	36	36			9.00								2		X								NEW SIGN IS LARGER AND SHOWS ONLY ONE SIDE ROAD LEFT; 2009 MUTCD SIGN CODE NEW SIGN INSTALLED AT NEW LOCATION	X		
		F	W16-8P	24	8			1.33																		INSTALL THE PLAQUE ON THE LEFT-SIDE POST		9	
SB	2.116	F	D1-1E	72	20		<--- HARTLAND ELEM. SCHOOL						1		X												TO BE REPLACED SLIGHTLY FURTHER AHEAD AT MP 2.045			
SB	2.045	F	VD1-2L	72	20			10.00								2		X								INSTALL 375 FT± SOUTH OF THE REMOVED SIGN AT MP 2.116; NOTE NEW SIGN CODE		10	
SB	1.939	F	R2-5A	24	30		REDUCED SPEED AHEAD						1		X												NOTE LOCATION AS A REFERENCE POINT FOR THE NEXT SIGN			
SB	1.918	F	W3-5	36	36			9.00								2		X								INSTALL 110 FT± SOUTH OF THE REDUCED SPEED AHEAD SIGN REMOVAL AT MP 1.939	X		
SB	1.873	F	W11-2	30	30		PEDESTRIAN SYMBOL			1				X												THIS ENTIRE ASSEMBLY WAS REPLACED IN 2010			
		F	W7-3A	24	18		NEXT 1/2 MILE (PLAQUE)			1																			
SB	1.812	F	R2-1	24	30		SPEED LIMIT 30						1		X												TO BE REPLACED FURTHER SOUTH AT MP 1.770			
SB	1.801	F	M2-1	21	15								1		X														
		F	M1-5	24	24								1																
		F	M2-1	21	15			2.19								1		X								**GREEN ON WHITE** "JCT"	X		
		F	M1-5	24	24			4.00																		VERMONT ROUTE 12			E-136B
SB	1.770	F	R2-1	30	36			7.50								1		X								NOTE: 1st SIGN IN THE REDUCED SPEED ZONE IS LARGER; INSTALL ACROSS FROM THE NB-FACING SPEED LIMIT 40		6	
							SHEET TOTALS	43.02	0.00	2	0	0	6	0	0	8		120.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	487.9	0.0	62	0	0	97	0	0	69		1035.0		0		0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **SPRINGFIELD-HARTFORD**
PROJECT NUMBER: **STPG SIGN(33)**
FILE NAME: **HARTLAND US-5 SB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
HARTLAND US-5 SB 6
PLOT DATE: **2/14/2012**
DRAWN BY: **M. MILLER**
CHECKED **A. GAMBLE**
SHEET **137** OF **162**