DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
HARTFORD SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	0.011	F	W-060	30	30		HIDDEN DRIVES	6.25								1		X								INSTALL 150 FT± SOUTH OF THE HILL 7% SIGN INSTALLED AT MP 0.039			E-154
SB	0.113	F	S3-1	36	36			9.0								2										THIS SIGN WAS MOVED TO THIS LOCATION FROM SB MM 0.075 - SEE PREVIOUS SHEET			
							SHEET TOTALS	~~6.25~~ 15.25	0.00	0	0	0	0	0	0	~~1~~ 3		15.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	144.5	0.0	17	2	2	28	0	0	27		405.0		0		0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: SPRINGFIELD-HARTFORD
PROJECT NUMBER: STPG SIGN(33)

FILE NAME: HARTFORD US-5 SB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
HARTFORD US-5 SB 6

PLOT DATE: 12/12/2011
DRAWN BY: M. MILLER
CHECKED A. GAMBLE
SHEET 161 OF 162