DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW SQUARE STEEL POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATIONS SHSM	SIGN DETAIL LOCATIONS PROJECT SHEET #	SIGN DETAIL LOCATIONS STANDARD SHEET #
NORWICH US 5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	4.220	A	N/A	24	30		WELL HEAD PROTECTION			1				X															
NB	5.720	A	W11-10	30	30								1		X														
		A	W16-2	24	18								1																
		A	W11-10	30	30			6.25								1		X								X		
		A	W16-2P	24	18			3.00																		X		
NB	6.120	A	W1-2L	30	30		LEFT CURVE						1		X														
NB	6.150	A	W1-2L	30	30			6.25								1		X									INSTALL 160' NORTH OF ORIGINAL SIGN LOCATION	X		
NB	6.600	A	M2-1	21	15								1		X														
		A	M1-5	30	24								1																
		A	M2-1	21	15			2.19								~~1~~ 2		X								BLACK ON WHITE	X		
		A	M1-6	30	24		0050 1411 0660	5.00			I	I	I														X	E-136C
NB	6.670	C	VR-017	24	30		LLL 24,000 LBS			1				X													KENDALL STATION RD TH-69			
NB	6.678	D	R1-1	30	30								1		X												KENDALL STATION RD TH-69 WITH MILE MARKER			
		D	R1-1	30	30		0050 1411 0668	6.25			I	I	I			1		X								X		
NB	6.710	A	VD1-1A	72	10		D-BOARD AND ROUTE MARKER ASSEMBLY						1		X														
							SHEET TOTALS	28.94	0.00	2	~~2~~ 0	~~2~~ 0	~~9~~ 7	0	0	5		75		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	128.2	0.0	6.0	0.0	0.0	31	0.0	0.0	16		240.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: NORWICH - FAIRLEE
PROJECT NUMBER: STPG SIGN (34)

FILE NAME: 10C334
PROJECT MANAGER: A.GAMBLE
DESIGNED BY: D.CROSSLEY
NORWICH U.S. 5 NORTHBOUND 2

PLOT DATE: 5/2/2011
DRAWN BY: D.CROSSLEY
CHECKED BY: QAU
SHEET 9 OF 65