DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW SQUARE STEEL POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
THETFORD US 5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.000	C	VD-024	60	7.5								1		X													
		C	VD-025	60	7.5								1															
		C	VD-700	6	10								1															
		C	VD-024	72	10		Thetford / Norwich Orange Co. / Windsor Co. 0050 0911 0000 / 0050 1411 0829	5.00								2		X								4	
		C	VD-025	72	10			5.00																			4	
		C	VD-700	6	10			0.42																				E-138
		C	VD-700	6	10			0.42																				E-138
NB	1.840	A	W10-3R	30	30		RAILROAD CROSSING			1				X														
NB	1.900	A	VD-062B	72	16		BUSINESS SIGN			1				X														
NB	1.960	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X												PAVILLION RD TH-44 (SOUTH)			
		C	VR-017	24	30			5.00								1		X										E-141
NB	1.960	D	R1-1	30	30		STOP			1				X													PAVILLION RD TH-44 (SOUTH)			
NB	2.540	A	R2-5A	24	30		SPEED LIMIT 40 REDUCED SPEED AHEAD						1		X														
		A	W3-5	36	36			9.00								2		X										X	
NB	2.605	A	VD-018	30	18								1		X													
							SHEET TOTALS	24.84	0.00	3	0	0	6	0	0	5		75		0	0	0	0	0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	243.9	0.0	25.0	2.0	2.0	65	0.0	0.0	28		420.0		4			364.8					

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: NORWICH - FAIRLEE
PROJECT NUMBER: STPG SIGN (34)

FILE NAME: 10C334
PROJECT MANAGER: A.GAMBLE
DESIGNED BY: D.CROSSLEY
THETFORD U.S. 5 NORTHBOUND 1

PLOT DATE: 5/2/2011
DRAWN BY: D.CROSSLEY
CHECKED BY: QAU