DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW SQUARE STEEL POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
THETFORD US 5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.870	A	D1-1M	72	10		^UP NORTH THETFORD 2						1		X													
		A	D1-1A	72	10		^UP FAIRLEE 8						1															
		A	D1-1A	72	10		^UP THETFORD HILL 2						1															
		A	D1-1A	72	10		^UP CHELSEA 23						1															
		A	D1-1A	72	10		LYME NH --->						1															
		A	M2-1	21	15			2.19								1		X						GREEN ON WHITE	X		
		A	M1-5A	30	24			5.00																			E-136B
NB	2.890	A	R2-1	24	30			5.00								1		X						INSTALL 10'+ SOUTH OF POLE #6/4	X		
NB	2.920	A	M4-14	24	12			2.00								1		X						BLACK ON WHITE	X		
		A	R8-3	24	24			4.00																INSTALL AT MIDPOINT OF SMALL ISLAND IN FRONT OF AUTOMOTIVE	X		
NB	2.940	A	R8-3	24	24			4.00								1		X						INSTALL BETWEEN IRVING SIGN AND NORTH END OF ISLAND	X		
NB	2.953	A	M3-4	24	12		ROUTE MARKER ASSEMBLY						1		X													
		A	M1-5A	30	24								1															
		A	M5-1	21	15								1															
		A	M3-1	24	12								1															
SIGN SUMMARY SHEET							SHEET TOTALS	22.19	0.00	0	0	0	9	0	0	4		60		0	0	0	0	0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	243.9	0.0	25.0	2.0	2.0	65	0.0	0.0	28		420.0		4		364.8						

PROJECT NAME: **NORWICH - FAIRLEE**
PROJECT NUMBER: **STPG SIGN (34)**
FILE NAME: **10C334**
PROJECT MANAGER: **A.GAMBLE**
DESIGNED BY: **D.CROSSLEY**
THETFORD U.S. 5 NORTHBOUND 3
PLOT DATE: **5/2/2011**
DRAWN BY: **D.CROSSLEY**
CHECKED BY: **QAU**
SHEET **21** OF **65**